

MAR 08 1999

MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON October 9, 1998

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

98 DEC 28 A8:37

For corners in Mecosta (County)	Located In: Aetna Twp.	Corner Code #
1. Public Land Survey	SEC 4 T13N R10W	G-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

*Joann Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3				●									
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James J. Keller, in a field survey on September 15, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- October 28, 1837, Abner E. VanNess, Deputy Surveyor G.L.O. "Set Post. Cor to Sect 3, 4, 9 & 10"  
10" Beech N6°E 11 Links (7.62')  
12" Beech S44°W 192 Links (126.72')
- March 23-24-25-26, 1896, Lyman W. June, County Surveyor (Record Book 1, P13, and Field Book 1, Pages 146-147)  
"Old Stake"  
26" Pine Stump S45°E 22 Links (14.52') "Old Rewitness"  
1/4 Post Sect. 3 & 10 East 40.24ch (2655.84')
- September 7, 1978, Gerald J. Gray, RLS #17741 (Survey L10 P624, Sh 1of2 and Survey L10 P615, Sh 2of2)  
Set 1/2" Iron Rod 20" Maple S50°W 40.45' Power Pole N50°E 41.00' 15" Maple S03°W 62.60'
- August 14, 1979, Gerald J. Gray, RLS #17741 (LCRC L1 P498) Found 1/2" Iron Rod  
20" Maple S50°W 40.45' Power Pole N50°E 41.00' 15" Maple S03°W 62.60'
- August 4, 1997, James J. Keller, RLS #10693 (FB 140, Pgs 37-38) Found 1/2" Iron Bent SE at SW Corner Section 3 (No Witnesses Given) Iron is S87°39'04"W 2652.20' from S1/4 Cor. Sec. 3-13-10


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- September 15, 1998, James J. Keller, RLS #10693 (FB 138-W, P62) Found Bent 1/2" Rebar 4" deep  
Found 60d SW Sd P.Pole N56°E 39.35' Found. 60d N Sd 16" Maple S09°W 62.60'  
Found 60d (grown over) NE Sd 21" Maple S53°W 40.50'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 1/2" Rebar as Best Evidence of the Original Corner and Set Remonumentation Monument as a Careful and Faithful Perpetuation of the Original Corner.

- Set BK Nail & Tag SE Sd Power Pole N56°E 39.80'
- Set 60d & Tag W. Sd 16" Maple S09°W 63.00'
- Set 60d & Tag NW Sd 21" Maple S53°W 41.40'
- Set 60d & Tag NE Sd 10" Wh. Pine N43°W 118.68'



Signed by James J. Keller  
Surveyor's Michigan License No. 10693

Date October 28, 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1976  
REVISED JAN. 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990  
James S. Knapp  
CHAIRMAN  
DATE OCT. 9, 1998

MAR 03 1999

SECTION

Oct-27-1998

JJK LJH TMB

