

SURVEY & REMONUMENTATION

APR 04 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

For corners in

Mecosta

Located In:

Corner Code

(County)

95 DEC 29 18:47

- | | | | | |
|---------------------------------------|---------|-------------|-------------|---------------|
| 1. Public Land Survey | Sec | T <u>13</u> | R <u>10</u> | G-7, Sec Corn |
| | | T _____ | R _____ | _____ |
| | | T _____ | R _____ | _____ |
| | | T _____ | R _____ | _____ |
| 2. Property Controlling
in Section | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |

James Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on July 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837, Abner VanNess, Deputy Surveyor, GLO Notes

Set Post Corner to Sections 15, 16, 21 and 22

Beech 12" S38°E 4 links

Maple 8" S53°W 14 links

1964, Carl Roser, Michigan State Highway Department

Found 1/4" x 2" Iron Bar 4" Deep in Centerline of East-West Road; in line with fence to North and

25 feet East of Tree Row to South

Oak 26" S10°W 85.75 feet

Apple 22" North 68.34 feet

Apple 18" N75°E 90.93 feet

1981, Jack Pierson, Survey Records

1/4" x 2" Iron

Same Bearing Trees as data in 1964

1991, James Keller, Field Notes

Set Nail 10" Cherry N52°W 48.74 feet

Set Nail 16" Oak S23°W 19.30 feet

Found Nail MSHD Tag in 34" Apple N08°E 68.45 feet

Found MSHD Tag in 28" Apple N80°E 91.31 feet

Northwest Corner Pole Barn S40°E 89.21 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2-1/4" Flat Stock 2.5 feet long in a nest of stones. Found 1-3/4" x 3.4 foot Sleigh Shoe 1 foot North and 0.4 feet East

Found Nail in 18" Oak S40°W 19.35 feet from Sleigh Shoe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner over 1-3/4" Sleigh Shoe

Found Nail 18" Oak S40°W 19.35 feet

Set Nail and Tag in 12" Elm N60°E 41.44 feet

Set Nail and Tag in 10" Apple N60°E 40.78 feet

Set Nail and Tag in 10" Oak S65°W 42.70 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-12, 1995

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 197

REVISED MAY 14, 1976

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1985

