

SURVEY REMONUMENTATION MECOSTA COUNTY REMONUMENTATION PROGRAM
CORNER APPROVED BY PEER GROUP ON DECEMBER 3, 1999

MAR 14 2000

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED FOR RECORD

For corners in **SECTION**

<u>MECOSTA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 13N R 10W	H-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

'99 DEC 10 P2:59

Joann Brown
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4 Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, JAMES G. KNAPP, in a field survey on MAY 12, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST IN JUNE 1837, CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM CORNER COMMON TO SECTIONS 34 AND 35, AND BEING 1.00 CHAIN (66.00 FEET) WEST OF STREAM 08 LINKS (5.28 FEET) COURSE - SOUTH, AND WITNESSED: BEECH 10" N09°E 16 LINKS (10.56 FEET)
 PINE 18" N23°W 27 LINKS (17.82 FEET)

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY WILLIAM G. TINGLEY, P.S. 30104, RECORDED ON OCT. 15, 1996, IN LIBER 12, PAGES 117 THRU 120, AND NOTES CORNER AS, "END 1 1/4" AXLE SHAFT", AND WITNESSED:

FND NAIL NE. SD. 4" MAPLE N45°W .13.70'
 FND NAIL E. SD. 14" OAK N45°E 18.65'
 SET N&T NE. SD. 6" OAK S45°E 22.35'
 SET N&T N. SD. 24" OAK S60°W 45.05'

**APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990**

James G. Knapp
 CHAIRMAN
 DATE DEC. 3, 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" X 2.8' IRON SHAFT, 6' NORTH OF OVERGROWN TRAIL, 72' WEST OF REMAINS OF FENCE - SOUTH, AND 90' WEST OF TRAIL CROSSING 6' STREAM.

FOUND REMAINS OF G.L.O. PINE STUMP AT AZ. 335°, 18.0 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13, 1/4 CORNER SECTION 34, T13N-R10W.
 FOUND 1 1/4" X 2.8' IRON SHAFT, 6' NORTH OF OVERGROWN TRAIL, 72' WEST OF REMAINS OF FENCE - SOUTH, AND 90' WEST OF TRAIL CROSSING 6' STREAM, AND IS ACCEPTED AS A CAREFUL AND PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. REMOVED THE 1 1/4" X 2.8' IRON SHAFT, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, PROTRUDING 4" ABOVE GROUND, WITH THE IRON SHAFT BURIED DEEPER ALONG SIDE, AND WITNESSED:
 FOUND NAIL IN S.E. SIDE OF 14" WHITE PINE AZ. 32°, 17.96 FEET
 SET 60d SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF 12" BLACK OAK AZ. 162°, 22.03 FEET
 FOUND SPIKE W/TAG NO. 30104 IN NORTH SIDE OF 16" BLACK OAK AZ. 252°, 45.47 FEET
 FOUND NAIL IN N.E. SIDE OF 4" MAPLE AZ. 306°, 13.53 FEET

Signed by James G. Knapp Date DECEMBER 3, 1999
 Surveyor's Michigan License No. 25853

