

SURVEY MECOSTA COUNTY REMONUMENTATION PROGRAM
REMONUMENTATION
CORNER APPROVED BY PEER GROUP ON OCTOBER 8, 1999

OCT 21 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED FOR RECORD

For corners in SECTION
MECOSTA
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	13N	R	10W	K-03
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

99 OCT 21 10:03

James Brown
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4 Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, JAMES G. KNAPP, in a field survey on MAY 29, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, ABNER E. VANNESS, SET POST ON OCT. 23, 1837. CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM WEST 1/4 CORNER, AND 39.905 CHAINS (2633.73 FEET) FROM NORTH 1/4 CORNER, SECTION 12, AND WITNESSED:
 BEECH 6" N62°W 10 LINKS (6.60 FEET)
 BEECH 8" N76 1/2°W 16 LINKS (10.56 FEET)

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, DATED AUG. 1919. CORNER NOTED AS BEING AT STATION 0+00, AND SHOWS A DISTANCE OF 2608.9' TO 1/4 CORNER COMMON TO SECTIONS 1 AND 12, AND WITNESSED:
 14" POPLAR N40 3/4°E 44'
 ANCHOR POST S00 1/2°E 25.7'

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, BY W. H. WRIGHT, CIRCA 1935, NOTE CORNER AS "SEC. COR. IRON STK." AND BEING 2615' TO NORTH 1/4 CORNER, SECTION 2.

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990

James S. Knapp
 CHAIRMAN
 DATE OCT. 8, 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 17" RE-BAR, BURIED 8" BELOW GRAVEL ROAD SURFACE, AT 24" DEEP FOUND 1 1/2" SQUARE HEAD BOLT, SURROUNDED WITH STONES, IN CENTER OF FIVE MILE ROAD (24' GRAVEL), AND IN LINE WITH 170TH. AVENUE (20' GRAVEL - NORTH) AND REMAINS OF FENCE - SOUTH.

SET SHORTEN REMONUMENTATION MONUMENT, WITH THE 1/2" RE-BAR INSIDE OVER THE 1 1/2" SQUARE HEAD BOLT, SURROUNDED WITH STONES, INSIDE OF A HIGHWAY MONUMENT BOX, 0.7' NORTH OF CENTERLINE, DURING BITUMINOUS PAVING OF FIVE MILE ROAD (21' BITUMINOUS) ON MAY 29, 1997.

MEASURED DISTANCE TO J-03 = 2528.46' AND TO L-03 = 2608.39'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-03, CORNER COMMON TO SECTIONS 1, 2, 11, AND 12, T13N-R10W.
 FOUND 1/2" RE-BAR, OVER A 1-1/2" SQUARE HEAD BOLT, SURROUNDED WITH STONES, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
 REMOVED THE 1/2" RE-BAR, AND PLACED OVER THE 1-1/2" SQUARE HEAD BOLT, SURROUNDED WITH STONES, A SHORTEN STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:
 FOUND SPIKE W/TAG 30104 IN SOUTH SIDE OF 24" ASH AZ. 78°, 91.86 FEET
 FOUND SPIKE IN EAST SIDE OF UTILITY POLE AZ. 196°, 97.06 FEET
 WEST END OF 12" X 30' CMP CULVERT AZ. 228°, 29.10 FEET
 WEST END OF 12" X 46' CMP CULVERT AZ. 340°, 50.80 FEET

Signed by James S. Knapp
 Surveyor's Michigan License No. 25853

Date OCTOBER 13, 1999

