

SURVEY &  
REMONUMENTATION

MECOSTA COUNTY REMONUMENTATION PROGRAM

JUL 06 1998

CORNER APPROVED BY PEER GROUP ON December 12, 1997

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

For corners in Mecosta (County)	Located In: Aetna Township	Corner Code #
1. Public Land Survey	SEC 14 T13N R10W	K-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

'98 APR 10 A10:35

*Journal Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James J. Keller, in a field survey on December 1 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- October 21, 1837, Abner E. VanNess, Deputy Surveyor G.L.O. "Set Qr. Sec. Post"  
8" Beech S37°W 3 Links (1.98')  
3" Beech N59°E 8 Links (5.28')
- July 5, 1973, Gerald J. Gray R.L.S. #17741 "East 1/4 Corner" (Unrecorded Survey)  
Tri-Beech N20°E 15.39'  
White Birch S10°E 23.54'  
14" Maple S50°W 26.0'
- March 24, 1975, Gerald J. Gray R.L.S. #17741 (L.C.R.C. Liber 1, Page 158) "Found 3/4" Iron"  
Tri-Beech N20°E 15.39'  
White Birch S10°E 23.54'  
14" Maple S50°W 26.0'
- March 26, 1996, James J. Keller R.L.S. #10693 (Survey Liber 12, Page 26) "No Witnesses Given"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 8, 1996, James J. Keller R.L.S. #10693 (Witness from Field Book 134W Page 14) "Found old Pine Stump South 9.18' to Center"

- Found 60d and Tag NW side 22" Beech of Tri Beech 22", 18", 10" N36°E 15.48'
- Found 60d and Tag E side 12" Birch S09°E 23.60'
- Found 60d and Tag SE side 14" Maple S65°W 26.09'
- Corner is in Line Old Stump Fences South and East and in Line Old Page Wire remnants North and West

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 3/4" Iron and set Remonumentation Monument as a careful and faithful perpetuation of the position of the original corner.

- Found 60d and Tag NW side 22" Beech of Tri Beech 22", 18", 10" N36°E 15.48'
- Found 60d and Tag E side 12" Birch S09°E 23.60'
- Found 60d and Tag SE side 14" Maple S65°W 26.09'
- Corner is in Line Old Stump Fences South and East and in Line Old Page Wire remnants North and West

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 343 of 1990

*James J. Knapek*  
CHAIRMAN  
DATE DEC. 12, 1997

Signed by James J. Keller Date December 12, 1997  
Surveyor's Michigan License No. 10693

