

MECOSTA COUNTY REMONUMENTATION PROGRAM

OCT 25 1999

CORNER APPROVED BY PEER GROUP ON FEBRUARY 13, 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

SECTION

For corners in

MECOSTA (County)

Located In:

Corner Code #

'99 AUG 27 A9:21

- 1. Public Land Survey T 13N R 10W K-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Joan Brown REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4 Lot No. Recorded Plat
5. Private Claims

Table with 13 rows and 12 columns (A-L) containing numbers 1-36.

I, JAMES G. KNAPP, in a field survey on OCTOBER 23, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST ON JUNE 20, 1837. CORNER POST PLACED 40.00 CHAINS (2640.00 Feet) FROM SOUTH 1/4 CORNER SECTION 36, AND WITNESSED: LYNN 10" N61°E 21 LINKS (13.86 FEET) WHITE ASH 16" N17°W 23 1/2 LINKS (15.51 FEET)

NOTES AT MONTCALM COUNTY REGISTER OF DEEDS OFFICE, FROM SURVEYOR'S FIELD BOOK, PAGE 2, NOTES CORNER AS, "HEMLOCK 24 S60°E 15, BEECH 18 S43°E 18, JULY 1892 FOUND STP OF PINE B.T. TOOK N.B.T. PINE STP 24 N55°E 24, JULY 1892 FOUND REMAINS OF HEMLOCK B.T. & STONE AND CROCKERY JUST DOWN BY CO. SURVEYOR OF MECOSTA COUNTY.

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY DONALD R. VERBA, P.S. 13603, ON APRIL 21, 1977, AND RECORDED IN LIBER 10, PAGE 393 - 394, AND NOTES CORNER AS, "S.W. SEC COR.", AND WITNESSED: NAIL - P. POLE S40°E 39.74' C/L SIGN POST N45°E 32.90' C/L SIGN POST S45°W 31.20'

CORNER USED, BY JAMES J. KELLER, P.S. 10693, AND NOTED AS, "FND. 3/4" I.P., 12" DEEP", AND WITNESSED:

- 4" POST N41°E 37.18'
P.POLE S32°E 54.79'
8" CHERRY S74°W 96.27'
12" ASH N72°W 119.70'

CORNER USED, BY WILLIAM G. TINGLEY, P.S. 30104, AND NOTED AS, "FND. 1" I.P., 18" LONG, DUG BELOW IT, FND. NEST OF STONE AND CROCKERY ", AND WITNESSED: NE COR. CONC. HDWALL S70°W 35.74'

- NW COR. CONC. HDWALL N70°W 39.5'
SET N & T NE SIDE P.P. S40°E 54.73'
TOP CENTER RISER BOX N45°E 33.54'

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp DATE FEB. 13, 1998


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1" X 18" LONG, IRON PIPE, OVER STONES AND CROCKERY, BURIED 12" DEEP AT FOUR WAY ROAD INTERSECTION".

COMMON LOCATION FOR STANDARD AND CLOSING CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 - CORNER COMMON TO SECTIONS 35 AND 36, T13N-R10W AND SECTIONS 1 AND 2, T12N-R10W. FOUND 1" X 18" LONG, IRON PIPE, OVER STONES AND CROCKERY, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. SET A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE 1" X 18" LONG, IRON PIPE, AND WITNESSED: FOUND P.K. NAIL WITH REMONUMENTATION TAG IN S.E. SIDE OF 4" POST AZ 41°, 37.18 FEET FOUND 60d SPIKE WITH TAG NO. 30104 IN N.E. SIDE OF P.POLE AZ. 148°, 54.79 FEET FOUND 60d SPIKE WITH REMONUMENTATION TAG IN EAST SIDE OF 8" CHERRY AZ. 254°, 96.27 FEET FOUND 60d SPIKE WITH REMONUMENTATION TAG IN NORTH SIDE OF 12" ASH AZ. 288°, 119.70 FEET



Signed by James G. Knapp

Date AUGUST 4, 1999

Surveyor's Michigan License No. 25853