

**SURVEY & REMONUMENTATION**  
**MECOSTA COUNTY REMONUMENTATION PROGRAM**  
**CORNER APPROVED BY PEER GROUP ON OCTOBER 8, 1999**

OCT 26 1999

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 COUNTY OF MECOSTA  
 RECEIVED FOR RECORD

'99 OCT 21 10:04

*James Brown*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION  
 For corners in:  
MECOSTA  
 (County)

Located in:

Corner Code #

- |                                       |                         |       |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey                 | T 13N R 10W             | L-03  |
|                                       | T _____ R _____         | _____ |
|                                       | T _____ R _____         | _____ |
|                                       | T _____ R _____         | _____ |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____ |
|                                       | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____ |
|                                       | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ |                         |       |
| 5. Private Claims _____               |                         |       |

I, JAMES G. KNAPP, in a field survey on MAY 29, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Only one corner may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, ABNER E. VANNESS, SET POST ON OCT. 23, 1837. CORNER POST PLACED 39.905 CHAINS (2633.73 FEET) FROM N.W. CORNER AND N.E. CORNER 12, AND WITNESSED: BEECH 8" N38°E 13 LINKS (8.58 FEET) IRONWOOD 6" S38°W 10 LINKS (6.60 FEET)

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, DATED AUG. 1919. CORNER NOTED AS BEING AT STATION 26+08.9, AND SHOWS A DISTANCE OF 2608.9' TO N.W. CORNER AND 2612.0' TO N.E. CORNER, SECTION 12, AND WITNESSED:

6" MAPLE N03°W 25.7'  
 8" MAPLE N72 1/2°E 124'

APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 of 1990

*James G. Knapp*  
 CHAIRMAN  
 DATE OCT. 8, 1999

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1" X 18" IRON PIPE, BURIED 15" BELOW GRAVEL ROAD SURFACE, AT 34" DEEP FOUND 1" X 4" X 12" IRON BAR, IN CENTER OF FIVE MILE ROAD (26' GRAVEL) AND IN LINE WITH FENCE NORTH AND SOUTH.

MEASURED DISTANCE TO K-03 = 2608.39 FEET AND TO M-03 = 2609.72 FEET.


FOUND REMAINS OF MAPLE STUMP AS CALLED FOR IN AUGUST 1919 NOTES AT AZ. 02°, 26.0 FEET

SET REMONUMENTATION MONUMENT, OVER THE 1" X 18" IRON PIPE, INSIDE OF A HIGHWAY MONUMENT BOX, IN CENTERLINE, DURING BITUMINOUS PAVING OF FIVE MILE ROAD (21' BITUMINOUS) ON MAY 29, 1997.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-03, 1/4 CORNER COMMON TO SECTIONS 1 AND 12, T13N-R10W. FOUND 1" X 18" IRON PIPE, BURIED 15" BELOW GRAVEL ROAD SURFACE, AT 34" DEEP FOUND 1" X 4" X 12" IRON BAR, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. REMOVED THE 1" X 18" IRON PIPE, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, OVER THE IRON BAR, WITH THE 1" X 18" IRON PIPE INSIDE THE MONUMENT, AND PLACED INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:

SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF 44" MAPLE	AZ. 02°, 63.63 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN SOUTH SIDE OF 36" MAPLE	AZ. 78°, 124.42 FEET (O.B.T.)
SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF UTILITY POLE	AZ. 178°, 85.68 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN N.W. SIDE OF UTILITY POLE	AZ. 232°, 33.04 FEET



Signed by James G. Knapp  
 Surveyor's Michigan License No. 25853

Date OCTOBER 13, 1999