

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>14</u> N. <u>9</u> W. <u>9</u> S. <u>9</u> W.	D-5, C-5,
2. PROPERTY CONTROLLING IN SECTION _____	<u>8</u> T. <u>14</u> N. <u>9</u> W. <u>9</u> S. <u>9</u> W.	15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 7, 19 80, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-5 Fd 1 1/4" pipe at corner probably as established in early county survey by L. June, although no record of it found. Conforms to U.S. data as returned in the examination of the original survey.
- C-5 Fd 1/2" rod at corner as restored and used in adjoining surveys by G. Gray, R.L.S. and others.
- 15 Set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>D-5 Fd. old 1 1/4" x 40" pipe added DNR mon & ced. post 5" R. Oak N30°W 11.7' 5" R. Oak Due E 11.2' 4" W. Oak N65°W 13.1' E-W rand Due S 46.8'</p>	<p>C-5 Fd 3/8" x 47" iron rod & 12" x 18" re-rod w/RLS cap added DNR mon & ced post 13" r. oak N45°W 17.82' 13" R. Oak Due E 20.22' 14" B Oak S60°W 21.70'</p>	<p>15 Set 5/8" x 34" re-rod w/RLS cap & ced post w/loc tag 6" W. Oak N85°W 10.2' 7" R. Oak Due S 16.8' 3" Maple S60°W 2.8' E-W rand Due S 23.4'</p>
---	--	---

SIGNED BY Kenneth J. Ostling DATE _____
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

MECOSTA COUNTY