

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>14</u> <sup>N.</sup> <del>S.</del> , R. <u>9</u> <sup>E.</sup> <del>W.</del>		<u>C-6, E-6, E-5</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____ E. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 7, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-6 Fd. corner as established by G. Gray during a survey in Sec. 18.
- E-6 Set corner in centerline of N-S road in line with old fence line west. Falls almost exactly at midpoint between section corners, and conforms to fence lines in n 1/2 mile. Could locate -o previous corner.
- E-5 Set corner by double proportionate measurement as related to U.S. data returned in 1854 examination of original survey by Brewer. Could locate no previous corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6	E-6	E-5
Fd 1/2" re-rod w/RLS cap added ced. post w/loc tag	Buried 5/8" x 34" re-rod w/RLS cap	Set DNR mon & ced post
14" W. Pine N30°W 43.4'	4" W. Oak N 75°E 47.55'	4" W. Pine S65°E 20.1'
14" & 8" W. Oak N85°E 51.4'	3" W. Pine S40°E 54.17'	9" W. Pine S15°E 24.3'
8" R. Oak S5°W 29.3'	Power Pole S80°W 55.77'	3" W. Oak N80°W 36.7'
	Set ced post w/loc tag	Ctr N-S dirt rd.
	Due E 33'	Due E 35'


SIGNED BY Kenneth J. Ostling DATE 10/10/80

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ MECOSTA COUNTY