

**SURVEY & REMONUMENTATION**

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

**OCT 29 1998**

**CORNER APPROVED BY PEER GROUP ON AUGUST 14, 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in MECOSTA Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 14N R 09W D-09  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

'98 OCT 19 A8:53

*James Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on JUNE 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Only one corner may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, ABNER E. VANNESS, SET POST IN JAN. 1838. CORNER POST PLACED 39.10 CHAINS (2580.60 FEET) FROM N.E. AND N.W. CORNER, SECTION 29, AND WITNESSED: BL. OAK " S26°E 11 LINKS (7.26 FEET)  
BEECH " N523°E 11 LINKS (7.26 FEET)

MECOSTA COUNTY ROAD COMMISSION NOTES, CIRCA 1935, NOTES CORNER AS, "1/4 COR. IRON STK".

CORNER RECORDED AS PER P.A. 74, BY BURT WICKHAM, JR., P.S. 17639, ON AUG. 7, 1987, IN LIBER 2, PAGE 182. CORNER NOTED AS, "FOUND PLOW POINT IN CENTERLINE OF EAST AND WEST GRAVEL ROAD & IN TREE ROW TO NORTH AND SOUTH HELD FOR CORNER", AND WITNESSED:  
NAIL IN NE. SIDE 18" OAK S50°E 35.90'  
NAIL IN NW. SIDE TWIN 18" & 12" MAPLE S25°W 40.00'  
NAIL IN E. SIDE 12" POPLAR N15°W 28.50'

CORNER CALLED FOR IN P.A. 132 OF 1970 SURVEY, BY WILLIAM G TINGLEY, P.S. 30104,, AS RECORD IN LIBER 12, PAGES 219 - 220, ON JUNE 10, 1997, AND IN LIBER 12, PAGES 247 - 248, ON AUG. 19, 1997 CORNER NOTED, AS, "N 1/4 CORNER SECTION 29 T14N-R9W", AND SHOWS A DISTANCE OF 2526.12' TO THE N.W. CORNER SECTION 29.

**APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990**


*James G. Knapp*  
CHAIRMAN  
DATE AUG. 14, 1998

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND PLOW POINT, BURIED 2" BELOW ROAD SURFACE IN EIGHT MILE ROAD AND IN LINE WITH OCCUPATION ROW NORTH AND SOUTH.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-09 1/4 CORNER COMMON TO SECTIONS 20, AND 29, T14N-R09W.  
FOUND PLOW POINT, BURIED 2" BELOW ROAD SURFACE IN EIGHT MILE ROAD, AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.  
PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, AND A HIGHWAY MONUMENT BOX, WHILE BITUMINOUS PAVING OF 8 MILE ROAD ON AUG. 9, 1995.  
SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF 10" WHITE BRICH AZ. 46°, 60.22 FEET  
SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF 26" RED OAK AZ. 134°, 36.54 FEET  
SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF 8" CHERRY AZ. 210°, 52.98 FEET  
SET 60d SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF 16" POPLAR AZ. 354°, 36.06 FEET



Signed by James G. Knapp Date OCTOBER 7, 1998  
Surveyor's Michigan License No. 25853

LIBER **101** PAGE **29**