

SURVEY & MECOSTA COUNTY REMONUMENTATION PROGRAM
REMONUMENTATION CORNER APPROVED BY PEER GROUP ON AUGUST 14, 1998

OCT 29 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED FOR RECORD

'98 SEP -8 A9:04

For corners in SECTION Located In: Corner Code #
 MECOSTA (County)

1. Public Land Survey T 14N R 09W E-09
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

4 Lot No. _____, Recorded Plat _____
 5. Private Claims _____

James S. Knapp
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on JUNE 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, ABNER E. VANNESS, SET POST IN JAN. 1838. CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM 1/4 CORNER COMMON TO SECTIONS 28 AND 29, AND WITNESSED: BEECH 20" N57°E 20 LINKS (13.20 FEET)
 BEECH 12" S42°W 30 LINKS (19.80 FEET)

ON APRIL 25 - 29, 1913, WALTER W. WILLITS, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK NO. 1, PAGE 162, (FIELD BOOK NO. 11, PAGE 63) NOTES CORNER AS, "IRON STAKE MAPLE 20"N50°E 97', AND SHOWS A DISTANCES OF 2670.00 FEET TO THE SOUTH 1/4 CORNER, AND 2725.00 FEET TO THE WEST 1/4 CORNER, SECTION 21.

ON OCT. 24 - 26, 1913, WALTER W. WILLITS, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK NO. 1, PAGE 163, (FIELD BOOK NO. 12, PAGES 28-33) NOTES CORNER AS, "IRON STAKE", AND SHOWS A DISTANCES OF 2670.00 FEET TO THE NORTH 1/4 CORNER, AND 2662.00 FEET TO THE WEST 1/4 CORNER, SECTION 28, AND WITNESSED:
 MAPLE 20" N50°E 97'
 ELM 6" N18°W 21'

MECOSTA COUNTY ROAD COMMISSION NOTES, CIRCA 1935, NOTES CORNER AS, "SEC. COR. IRON STR. AND TILE".

CORNER CALLED FOR IN MICHIGAN STATE HIGHWAY DEPARTMENT PLANS FOR RELOCATION OF M-20, PROJECT No. F-308, DATED 1946 AND NOTED AS, "1" PIPE", AND SHOWS A DISTANCES OF 2723.92 FEET TO THE WEST 1/4 CORNER, SECTION 21, AND WITNESSED:
 S64°-30'W 61.40' 5" ELM
 S11°W 67.75' 18" ELM
 N11°W 65.53' 4" MAPLE

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 348 of 1990

James S. Knapp
 CHAIRMAN
 DATE AUG. 14, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2 1/2" X 1/2" IRON BAR, (GRADER BLADE), BURIED 2" BELOW ROAD SURFACE IN EIGHT MILE ROAD, AND IN LINE WITH REMAINS OF FENCE ROW, NORTH AND SOUTH.

CORNER IS 200 FEET EAST OF 48" C.M.P. CULVERT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-09 CORNER COMMON TO SECTIONS 20, 21, 28, AND 29, T14N-R09W.
 FOUND 2 1/2" X 1/2" IRON BAR, (GRADER BLADE), BURIED 2" BELOW ROAD SURFACE IN EIGHT MILE ROAD, AND IS ACCEPTED AS THE AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.
 PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, AND A HIGHWAY MONUMENT BOX, WHILE BITUMINOUS PAVING OF 8 MILE ROAD ON AUG. 9, 1995.
 SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF 6" MAPLE AZ. 0°, 54.62 FEET
 SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF 10" POPLAR AZ. 149°, 75.99 FEET
 SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF 16" MAPLE AZ. 198°, 68.81 FEET
 SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF 6" WHITE PINE AZ. 202°, 47.24 FEET
 SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF UTILITY POLE AZ. 317°, 53.73 FEET



Signed by James S. Knapp Date SEPTEMBER 1, 1998
 Surveyor's Michigan License No. 25853