

REMONUMENTATION

MECOSTA COUNTY REMONUMENTATION PROGRAM

NOV 18 1997

CORNER APPROVED BY PEER GROUP ON DECEMBER 9, 1993

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

For corners in

MECOSTA
(County)

Located In:

Corner Code #

'97 NOV 10 P 3:09

- | | | | | | |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 14N | R | 09W | I-01 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Sec. | S | T | R | | |
| | S | T | R | | |

James Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4 Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JAMES G. KNAPP, in a field survey on SEPTEMBER 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, ADNER E. VANNESS, SET POST IN JAN. 1838. CORNER POST PLACED 38.85 CHAINS (2564.10 FEET) FROM 1/4 CORNER COMMON TO SECTIONS 2, AND 3, AND BEINGS 60 LINKS (39.60 FEET) EAST OF POST TO SECTIONS 34 AND 35, T15N-R09W, AND WITNESSED:

BEECH 18" S66°E 31 LINKS (20.46 FEET)

PINE 20" S15°W 36 LINKS (23.76 FEET)

IN 1895, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE COLFAX TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R09W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 281 AND 282. CORNER NOTED AS "REWITNESS - SET BY ORIGINAL FROM 14-9", AND WITNESSED AS, "PINE STUMP 18 N40°W 25 LINKS (16.50 FEET)".

"PINE STUMP 16 N33°E 64 LINKS (42.24 FEET)".

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
CHAIRMAN
DATE DEC. 9, 1993

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF ANY CORNER FOUND.

SET STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AT CALLED FOR G.L.G. FALLING, 60 LINKS (39.60') EAST OF STANDARD CORNER OF SECTION 34 AND 35, T15N-R09W, AND ON LINE BETWEEN S.W. CORNER AND SOUTH 1/4, SECTION 35, T15N-R09W.

CORNER IS 2' NORTH OF CENTER OF 12 MILE ROAD (22' GRAVEL), AND 40' EAST OF CENTER OF 140TH. AVENUE (24' GRAVEL - NORTH), AND 20' WEST OF FENCE ROW - SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


I-01 - CORNER COMMON TO SECTIONS 2 AND 3, T14N-R09W.

SET STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHED OF THE POSITION OF THE ORIGINAL CORNER AND WITNESSED:

SET 60d SPIKE W/REMONUMENTATION TAG IN S.W. SIDE OF UTILITY POLE	AZ. 140°	158.42 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF 8" MAPLE	AZ. 182°	84.60 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF UTILITY POLE	AZ. 244°	190.36 FEET
CORNER COMMON TO SECTIONS 34 AND 35, T15N-R09W (MECOSTA COUNTY REMONUMENTATION MONUMENT)	AZ. 270°	39.60 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF UTILITY POLE	AZ. 308°	182.12 FEET

Signed by James G. Knapp Date NOVEMBER 7, 1997

Surveyor's Michigan License No. 25853



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

ADAPTED FOR WORD PROCESSING MARCH, 1991