

**SURVEY &
REMONUMENTATION**

MECOSTA COUNTY REMONUMENTATION PROGRAM

FEB 26 1998

CORNER APPROVED BY PEER GROUP ON DECEMBER 9, 1993

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'97 DEC 22 AM 8:43

SECTION

For corners in

MECOSTA (County)	Located In:	Corner Code #
1. Public Land Survey	T 14 N R 09 W	K-01
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

James Brown
REGISTERED DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on NOVEMBER 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: ONLY ONE CORNER MAY BE RECORDED ON THIS CERTIFICATE.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, ABNER E. VANNESS, SET POST IN JANUARY, 1838, CORNER POST PLACED 40.50 CHAINS (2673.00 FEET) FROM 1/4 CORNER COMMON TO SECTIONS 1, AND 2, AND BEING 308 LINKS (203.28 FEET) WEST OF POST TO SECTIONS 35 AND 36, T15N-R09W, AND WITNESSED: PITCH PINE 18" S35°E 37 LINKS (24.42 FEET)
BEECH 20" S52°W 31 LINKS (20.46 FEET)

MECOSTA COUNTY ROAD COMMISSION, NOTES BY W. H. WRIGHT, COUNTY ENGINEER, DURING A ROAD SURVEY IN JULY 1936, NOTES CORNER AS, "IRON STAKE", AND BEING 116.0 FEET WEST OF SECTION CORNER 35 AND 36, T15N-R09W.

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY THOMAS J. MUELLER, P.S. 25861, ON OCT. 23, 1979, AND RECORDED IN LIBER 10, PAGE 784, AND NOTES CORNER AS, "SET 5/8" IRON W/RLS CAP".

CORNER RECORDED AS PER P. A. 74 OF 1970, BY, THOMAS J. MUELLER, P.S. 25861, ON OCT. 23, 1979, AND RECORDED IN LIBER 1, PAGE 525, AND CORNER NOTED AS, "SET 5/8" x 18" IRON W/RLS CAP @ INT. OF TWP. LINE AND CENTERLINE OF ROAD TO SOUTH, 111.36' W. OF 5/8" IRON", AND WITNESSED:

12" TRIPLE MAPLE	N17°W	99.11'
16" TRIPLE MAPLE	S55°W	36.00'
16" POPLAR	EAST°	124.10'
FE. POST	N11°E	29.97'

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
CHAIRMAN
DATE DEC. 9, 1993

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" X 18" RE-BAR, BURIED 4" BELOW ROAD SURFACE IN CENTER OF 12 MILE ROAD (24' GRAVEL), AND IN LINE WITH CENTER OF 130TH. AVENUE (22' GRAVEL - SOUTH), AND 115 FEET WEST OF 130TH. AVENUE (22' GRAVEL - NORTH).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K - 01 CORNER COMMON TO SECTION 1, AND 2, T14N-R09W
FOUND 5/8" X 18" RE-BAR, AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.
REMOVED THE 5/8" X 18" RE-BAR, AND SET IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, WITH THE 5/8" X 18" RE-BAR INSIDE THE MONUMENT, AND WITNESSED:

CORNER COMMON TO SECTIONS 35 AND 36, T15N-R09W (MECOSTA COUNTY REMONUMENTATION MONUMENT)	AZ. 92°	111.36 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE 8" MAPLE (CLUMP OF 5)	AZ. 144°	129.27 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN N.W. SIDE 6" TRIPLE MAPLE	AZ. 238°	138.46 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN S.W. SIDE 18" MAPLE	AZ. 343°	98.15 FEET



Signed by *James G. Knapp* Date NOVEMBER 19, 1997
Surveyor's Michigan License No. 25853