SURVEY & REMONUMENTATION STATE OF MICHIGAN COUNTY BY MECOSTA COUNTY BY MECOSTA.

MECOSTA COUNTY REMONUMENTATION PROGRAM RECEIVED FOR RECORD

LAND CORNED RECORD COMMISSION Corner approved by Peer Group on January 13, 1994 94 AUG -3 P1:37 or corners in REGISTER OF DEFIIS Located In: Corner Code # Mecosta T<u>14 N</u>R <u>10 W</u> Public Land Survey Sec A-1. Mecosta Two . Property Controlling in Section Register of Deeds Stamp & File Number Miscellaneous Property in Sec. ___ Recorded Plat 1 Å CDEFGHIJKLM . Private Claims _ 2 6 5 4 9 1 3 Δ 7 8 Q 12 a field survey on <u>April 2, 1994</u> Thomas H. Sage o hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned 5 I lines 1 and 2 above were in conformance with regulations and rules therefore as required in the 18 15 13 6 17 urrent manual of survey instructions of the United States Department of the Interior, Bureau of Land 7 lanagement or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 bove were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a 8 10 20 21 22 23 24 court of Law; established, re-established, monumented, re-monumented, recovered, found as 9 xpressed below: າດ 30 29 28 27 26 25 IOTE: Not more than 4 corners, all in the same town and range, may be recorded 11 on this certificate. 31 35 36 12 32 33 34 Description of original monument and accessories and/or subsequent restoration: September 26, 1837, John Hodgson, Deputy Surveyor, GLO Notes, Volume 2, page 223 Set Post Maple 8" N58°E 13 links Maple 10" S65°W 17 links October 22, 1906, Lyman W. June, Mecosta County Surveyor, Field Book 7, page 158, Record Book 1, Page 143 Set Iron Shaft (no witnesses listed) 916-1917 Vintage (exact date unknown), Lyle Shepherd, Newaygo County Surveyor Surveyed the West line of Section 6 and intersected the Corner East .06 chains. Distance 82.63 chains from the Southwest Corner. His notes do not indicate what monuments the Northwest Corner. Pine Stump 18" N62-1/2°W 25 links (16.5 feet)
Pine Stump 24" N53°W 46 links (30.4 feet) 46 links (30.4 feet)

1976 +/-, Ferris State College, Student Surveyors Senior Project, Found 2" x 2" Iron Shaft in intersection of 12 Mile Road and Newcosta Avenue. Twin Oak 14" N08°W 43.49 feet Oak 28" S71°E 35.45 feet Twin Maple 8" \$39°W 36.65 feet

N48°W 44.53 feet Aspen 12" lune 16, 1993, Thomas H. Sage, LS #33139, LCRC Liber 2, page 398

Found 2" x 2" Iron Shaft at the intersection of 12 Mile Road and Newcosta Avenue. Oak 16" N45°W 65.25 feet, Set Nail with Tag #33139 in Westside

Twin Oak 18" N8°W 43.25 feet, Nail in Eastside

33139 AND SURVEY Oak 24" S71°E 35.50 feet, Nail in Southside

Maple 8" S39°W 36.70 feet, Nail in Eastside

Description of corner evidence found and/or method applied in restoring or reestablishing corner: AND SUPPLY STATES AND Shepherd's witnesses listed above.

Remains of Pine Stump, N60°W 16.5 feet +/- (measurement to face of stump) Remains of Pine Stump, N50°W 30.4 feet +/- (measurement to face of stump)

 Description of monument for corner and accessories established to perpetuat Removed the 2" x 2" x 40" Iron Shaft and set a Remonumentation Monumer 	
Remains of Pine Stump N60°W 16.5 feet +!-	Approved by Mecosta co. Peer Gro
Remains of Pine Stump N50°W 30.4 feet +/-	N ACCORDANCE WITH P.A. 345 of 1990

N45°W 65.25 feet, Nail with Tag #33139 in Westside Oak 16"

Twin Oak 18", N8°W 43.25 feet, Nail in Eastside Oak 24" S71°E 35.50 feet, Nail in Southside Maple 8" \$39°W 36.70 feet, Nail in Eastside

ames y. Z CHAIRMAN

SAGE

LAND SURVEYOR

33139

NO.

this monument is accepted as a caref	ul and faithful perpetuation	n of the origin	nal corner.
Chis monument is accepted as a caref		Date	(11+7 10 1994
Surveyor's Michigan License No.			FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS.

Part A. (Continued from Front Side)

A Certificate of Survey by Gerald J. Gray, P.S. 17741, Recorded in Liber 10, Page 753, on Aug. 14, 1979, notes corner as "Found 2" Solid Bar", and Witnessed:

63.35' \$40°W 6" Pine
33.90' N50°W Fence Post
83.84" \$45°E 6" Pine

A Land Corner Recordation Certificate by Duane F. Wood, P.S. 24625, Recorded in Liber 2, Page 144 on Sept. 30, 1986, notes corner as "2" Solid Steel Bar", and Witnessed:

6" Pine S40°W 63.35' F.Post N45°W 36.0'. 8" Pine S45°E 88.4'