

**SURVEY & REMONUMENTATION COMMISSION**  
**APR 10 1995**

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

Corner approved by Peer Group on February 10, 1994

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF MECOSTA  
 RECEIVED FOR RECORD

or corners in  
 Mecosta (County) Located In: Corner Code #

Public Land Survey Sec. T 14 N R 10 W A-2 Mecosta Twp  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

'94 AUG -3 P1:38

*Carl Waldron*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Thomas H. Sage a field survey on April 2, 1994,  
 I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:  
 September 5, 1837, John Hodgson, Deputy Surveyor, GLO Notes, Volume 2, Pages 225 and 226  
 Set Post 40 chains North of Southwest Section Corner

Beech 12" S41°W 21 links  
 Beech 12" N79°W 36 links  
 1916 - 1917, Vintage (exact date unknown), Lyle Shepherd, Newago County Surveyor  
 Surveyed West Section Line, Field Book 36, Pages 112 and 113. His notes do not indicate what monuments this corner. Corner is 40.91 chains North of Southwest Section Corner. Witness: Pine Stump Northwest 1/2 link.  
 December 1965, George Blass. Found 1" x 18" Iron Pipe 2 feet East of East Wheel Track of North-South Trail Road in 3 foot cut and in line with old fence line to the East; and 6 feet North of new fence to the East  
 R. Oak 14" S67°W 37.55 feet  
 R. Oak 14" N73°W 68.20 feet  
 Maple 6" N47°E 54.45 feet

March, 1979, Duane Wood, Recorded Survey, Liber 10, Page 977  
 July, 1979, Duane Wood, Recorded Survey, Liber 10, page 767  
 September, 1986, Duane Wood, LCRC, Liber 2, Page 129

Found 3/4" Pipe  
 Maple 10" West 37.24 feet  
 Maple 15" N50°E 26.98 feet  
 Oak Tree S60°W 37.49 feet  
 June 3, 1993, Thomas H. Sage, LCRC, Liber 2, Page 398  
 Found 3/4" Pipe on Eastside of Newcosta Avenue (Trail Road). Pipe is located 6 feet North of old fence posts to the East (E-W 1/4 Line Fence)

Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 May 31, 1993, I found a 3/4" Pipe on Eastside of Newcosta Avenue (Trail Road).  
 Pipe is located 6 feet North of old fence posts to the East and 14 feet North of new fence. Found following witnesses:  
 Maple 20" N50°E 26.95 feet, Nail in Southside  
 Maple 12" West 37.25 feet, Nail in Southside  
 In comparing my distances along the West Section Line and the East-West 1/4 Line of Section 6 with the distances of George Blass's 1965 Section breakdown, our distances match within acceptable tolerances.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Removed the 3/4" Pipe and set a Remonumentation Monument at the position of the 3/4 Pipe on April 2, 1994.  
 Maple 20" N50°E 26.95 feet, Nail in Southside  
 Maple 12" S40°W 42.10 feet, Nail with Tag #33139 in Westside  
 Pine 10" S40°E 36.45 feet, Nail with Tag #33139 in Westside  
 Maple 12" West 37.30 feet, Set Nail with Tag #33139 above Old Nail in Northside

Monument is accepted as careful and faithful perpetuation of the position of the original corner.

Signed by Thomas H. Sage Date MAY 10, 1994

Surveyor's Michigan License No. 33139

APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 of 1990

*James S. Knapp*  
 CHAIRMAN  
 DATE FEB. 10, 1994

