

SURVEY & REMONUMENTATION MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON Nov 2, 1995

OCT 29 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

SECTION
For corners in

Mecosta (County)	Located In: Mecosta Twp	Corner Code #
1. Public Land Survey	Sec. 8 T 14N R 10W	C-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous S Property in Sec.	T R	
	S T R	

'98 SEP -8 A9:04

James Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James J. Keller, in a field survey on June 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
4th Quarter 1839, Abner E. VanNess, Deputy Surveyor GLO "Set Cr. Sec. Post"
10" Beech N32-1/2°E 13 links (8.6')
6" Beech South 22 links (14.52')

June 10 & 11, 1896, Lyman W. June, County Surveyor (Survey Record Book 1, P18) (Field Book 1, P76) "R.R. Rail for corner"

January 16, 1976, Norman L. Ochs, RLS #22439 (LCRC L 1, P194) "Found R.R. Rail"
Tri-W Oak 12"-16"-8" N55°W 33.38'
Twin W Oak 18"-8" S32°W 40.66'
6" W Pine N66°E 64.98'

June 16, 1979, Robert L. Wetherall, RLS #24624 (Survey L 10, P736)
W Oak Clump N55°W 33.38'
10" W Oak S32°W 40.65'
6" W Pine N66°E 64.98'

May 26, 1992, John E. McLane, RLS #28415 (Survey L 11, P532) "Found R.R. Rail at road edge."
6" White Pine N66°E 64.98'
R/W Capped Iron Az. 138° 46.67'
10" White Oak S32°W 40.65'
W Oak Clump N55°W 33.38'

June 8, 1995, James J. Keller, RLS #10693 (Field Book 113-W P116) "Found R.R. Rail leaning West"
Fnd 5/8"x 18" rebar 12" deep along base of 2" X 3.7' R.R. rail fitting McLane's distance to center, under a 3-1/2" X 3-1/2" X 7" granite stone
Fnd nail E sd 3"-8" W Oak clump N47°W 33.33'
Fnd nail SE side Twin 18" W Oak & set 60d above S37°W 40.63'
Fnd 1/2" Rebar & cap #28415 S40°E 46.61'
Set 60d SE sd 12" W Oak N58°E 52.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 26, 1995, James J. Keller, RLS #10693 (Survey L 11 P931-932-933)
Fnd 5/8" Rebar at E. Ed 3" R.R. Rail bent SW 13" deep
Fnd nail E sd 3"-8" White Oak clump N47°W 33.33'
Set nail SE sd 12" White Oak N58°E 52.52'
Fnd 1/2" Rebar & Cap #28415 S40°E 46.61'
Fnd nail & set nail above SE sd Twin 18" White Oak S37°W 40.63'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 5/8" Rebar at East edge R.R. Rail leaning West and set Remonumentation Monument 1.1' deep in monument box as a careful and faithful perpetuation of the location of the original corner.
Fnd 60d and Set 60d & tag above E sd 3"-8" White Oak clump N47°W 33.33'
Fnd 60d and set 60d and tag SE sd 12" White Oak N58°E 52.52'
Fnd 1/2" Rebar & Cap #28415 S40°E 46.61'
Fnd nail and set tag SE sd Twin 18" White Oak S37°W 40.63'
Set 1" round Ip and Cap #10693 N51°E 47.37'


Signed by James J. Keller Date November 13, 1995

Surveyor's Michigan License No. 10693

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James J. Knapp
CHAIRMAN
DATE Nov. 2, 1995

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JUNE 14, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983