

OCT 26 1999

MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON August 13, 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

For corners in

Mecosta (County)

Located in:

Mecosta Twp.

Corner Code #

Table with 3 columns: Description, Location (SEC 17 T 14N R 10W), and Corner Code # (C-6). Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

'99 OCT -8 P3:04

James Brown REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. Cell 6,17 contains a black dot.

I, James J. Keller, in a field survey on August 4, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- March 2, 1838, Abner E. Van Ness, Deputy Surveyor GLO "Set Or Sec Post"
November 17, 18, 19, 20, 1902, Lyman W. June, County Surveyor (Record Book 1 P118) (Field Book 0, P32 not found)
November 21, 1902, Lyman W. June, County Surveyor (Record Book 1 P119) (Field Book 0, P48 Not Found) "Old Stake"
July 31, 1911, Lyman W. June, County Surveyor (Record Book 1 P158) (Field Book 9 P76-77) Road Survey along E. Line of SE 1/4 18-14-10. No Witnesses Given.
February 6, 1976, James E. Evans, RLS #22431 (Survey L10 P334-337) "Set 2" Pipe"
June 4, 1979, Norman L. Ochs, RLS #22439 (Survey L10 P713-715) "Set 2" Pipe"
June 13, 1979, Norman L. Ochs, RLS #22439 (LCRC L1 P489) "Set 2" Pipe 15" Long as Prorated against L.W. June Survey of 1902"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


August 4, 1999, James J. Keller, RLS #10693 (FB 138-W P93) "Found 2" Pipe, 6" Deep"
Found 60d & Tag #22439 S Sd 8-12" Tw W. Oak with Barb N89°W 51.46'
Found 60d W Sd 28" Maple N22°E 45.71'
Found 60d & Tag #22439 NW Sd 12-14" Tw R. Oak N64°E 39.45'
Found 60d & Tag #22439 E Sd 26" B. Oak S09°E 66.14'
C/L Two Track W 6'
Note: Found 2 Blazes at 1' & 4' Heights all trees listed

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 of 1990

James J. Knapp CHAIRMAN DATE AUG. 13, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Cap on top of 2" IP and cemented them together as a careful and faithful perpetuation of the original corner
Found 60d & Tag #22439 and set 60d and tag above S Sd 8-12" Tw W. Oak with Barb N89°W 51.46'
Found 60d and set 60d and tag above W Sd 28" Maple N22°E 45.71'
Found 60d & Tag #22439 and set 60d and tag above NW Sd 12-14" Tw R. Oak N64°E 39.45'
Found 60d & Tag #22439 and set 60d and tag above E Sd 26" B. Oak S09°E 66.14'
C/L Two Track W 6'
Note: Found 2 Blazes at 1' & 4' Heights all trees listed



Signed by James J. Keller
Surveyor's Michigan License No. 10693

Date September 29, 1999

SURVEY &  
REMONUMENTATION

OCT 28 1999

SECTION

9 - 9 - 1999

LJH

