

**SURVEY & MECOSTA COUNTY REMONUMENTATION PROGRAM**  
**REMONUMENTATION**

Corner approved by Peer Group on May 12, 1994

STATE OF MICHIGAN  
 COUNTY OF MECOSTA  
 RECEIVED FOR RECORD

APR 10 1995

Filing Requirement of Act 74, Mich. P.A. 1970

'94 AUG -3 P1:38

corners in \_\_\_\_\_  
 Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

**COMMISSION**

*Carl Waldron*  
 REGISTER OF DEEDS

Public Land Survey Sec. T 14 N R 10 W D-1 Mecosta Twp  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Thomas H. Sage a field survey on June 2, 1994

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as recorded below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration: **Section corner was not established by the GLO Survey. Corner to be established on Section Line, halfway between the northwest and Northeast Section Corners.**

**6 +/-, Ferris State College, Student Project on Sleigh Shoe**

- Poplar 8" N15°W 45.90 feet
- Beech 12" S45°E 41.13 feet
- Pole S22°E 82.10 feet
- Beech 12" S37°W 44.62 feet

February 19, 1976, Douglas W. Hooth, LS #7966, LCRC Liber 1, Page 232

Found Sleigh Shoe (2-1/2" x 1" iron bar) 20" deep 9 feet East of 225th Avenue in Centerline of 12 Mile Road. Raised with 1" Iron Bolt.

- Maple 14" S46°E 51.70 feet
- Oak 8" S30°W 51.59 feet
- 7" Maple N05°W 28.26 feet

December 15, 1978, Thomas H. Sage, Found 1" Iron Bolt with Nut, 5" Deep, 2 Feet North of the Centerline of 12 Mile Road, and 2 feet West of the extension of the Centerline of 225th Avenue.

- Poplar 8" N15°W 45.10 feet
- Maple 14" S45°E 41.00 feet
- Power Pole S20°E 81.90 feet

Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 1" x 12" Bolt with Nut 1" deep, directly over Sleigh Shoe. Found three 6"-8" stones around the base of Sleigh Shoe. Also found the following witnesses:

- Poplar 12" N15°W 45.90 feet Nail in West side
- Maple 24" S45°E 41.05 feet Nail in West side
- Pole S20°E 82.26 feet Long Nail
- 82.05 feet Flush Nail
- Maple 20" S46°E 51.72 feet Nail in West side
- Oak 20" S30°W 51.6 +/- to Centerline of Tree
- Poplar 8" N5°W 28.26 feet Nail with MDOT Tag in West side

moved the 1" Bolt and Sleigh Shoe and set a remonumentation monument. The monument is approximately 10" deep.

Description of monument for corner and accessories established to perpetuate locating the position of the corner: **Re-monumentation Monument.**

- win Oak 12" N20°E 52.16 feet 60 d Nail with Remonumentation Tag East Side
  - ower Pole S20°E 82.03 feet 60 d Nail with Remonumentation Tag West Side
  - ak 20" S30°W 51.55 feet 60 d Nail with Remonumentation Tag West Side
  - aple 5" N45°W 49.23 feet 60 d Nail with Remonumentation Tag East Side
- s Monument is accepted as the best available evidence of the position of the corner.

Recorded by Thomas H. Sage Date June 10, 1994

Surveyor's Michigan License No. 33139

APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 of 1990

*James H. Knapp*  
 CHAIRMAN  
 DATE MAY 12, 1994

