

**SURVEY &
REMONUMENTATION**

MECOSTA COUNTY REMONUMENTATION PROGRAM

APR 04 1996

CORNER APPROVED BY PEER GROUP ON DEC. 7, 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

For corners in
Mecosta
(County)

Located In:

Corner Code #

95 DEC 19 P1:52

1. Public Land Survey	Sec 8	T 14N R 10W	E-4
		T R	
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

Jessie Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James J. Keller, in a field survey on June 8 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

20 March 1838, A.E Van Ness Deputy Surveyor, G.L.O. notes "Set Qr. Section Post", 8" Sugar S24°E 8 Links, 6" Sugar N79½°W 17 Links
June 10 & 11 1896, L.W. June, County Surveyor, County Surveyor's record, Pg 18 "Old Post" Field Book 1 pg 76
April 22 1897, L.W. June County Surveyor, County Surveyor's Record, Pg 25 " Old Stake" Field Book 2 Pg 32
23 May 1992, John E. Mc Lane #28415 (L. 11, P. 532) Found 1/2" Iron at intersection 220th Avenue and Hayes Road.
12" White Pine Az. 53° 55.02'
24" White Oak Az. 124° 66.95
22" Cedar Az. 250° 40.35'
20" Walnut Az. 315° 50.12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 8 1995 James J. Keller #10693, found 5/8" rebar with cap #17741-24625 4" deep in intersection of Hayes Road & 220th Avenue Fitting McLane Distance from Center as well as McLane's Witness's, Rebar is over old rusty 1" round x 26" IP with Survey Tape around top, 18" below surface.

Found 30d SW. side 16" Ash N44°W 50.11'
Found 30d S.E. side 14" White Pine N56°E 54.97'
Found 60d West side distribution pole (CPCO) S28°E 66.59'
Found 30d NE side 28" White Oak S55°E 62.03'

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990
James J. Knapp
CHAIRMAN
DATE DEC 7, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation monument 0.8" deep in monument box and accepted as a careful and faithful perpetuation of the position of the original corner.

Found 30d and set 60d and tag SW. side 16" Ash N44°W 50.11'
Found 60d and set 60d and tag West side distribution pole (CPCO) S28°E 66.59'
Found 30d and set 60d and tag NE side 28" White Oak S55°E 62.03'
Found 30d and set 60d and tag SE side 14" white Oak N56°E 54.97'
Found 60d and set tag SE side 22" Cedar with Blaze S45°W 48.12'
Found 30d and set 60d and tag SE side 12" White Pine N52°E 55.05'
Found 60d and set tag SW side 22" Walnut N45°W 50.13'
Found 30d and set 60d and tag SW side 22" Cedar S67°W 40.60'

Signed by *James J. Keller* Date 8 June 1995

Surveyor's Michigan License No. 10693

