

MAR 14 2000

MECOSTA COUNTY REMONUMENTATION PROGRAM

SECTION CORNER APPROVED BY PEER GROUP ON NOVEMBER 18, 1993

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

'99 DEC 10 P2:59

Jeanne Brown REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in MECOSTA (County) Located in: Corner Code #

- 1. Public Land Survey T 14N R 10W F-01
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

4 Lot No. Recorded Plat
5 Private Claims

I, JAMES G. KNAPP, in a field survey on NOVEMBER 5, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: CORNER WAS NOT SET BY GOVERNMENT LAND OFFICE DEPUTY SURVEYORS

FERRIS STATE COLLEGE, SENIOR PROJECT, CIRCA 1976, NOTES CORNER AS, "FOUND NOTHING IN THIS AREA AND COULD NOT LOCATE OLD WITNESSES", AND SHOW A DISTANCE OF 177' FROM OLD FENCE - NORTH TO CENTER OF 215TH AVENUE - SOUTH.

CORNER RECORDED AS PER P.A. 74 OF 1970, BY DOUGLAS W. HOOTH, P.S. 7966, ON APRIL 1, 1976, IN LIBER 1, PAGE 230, AND NOTED AS, "SET N 1/4 SEC 4, T14N, R10W IN LINE BETWEEN THE S 1/4 COR, SEC 33 T15N, R10W AND THE SE COR, SEC 33 T15N, R10W AND IN LINE S,LY WITH OLD SURVEY POINT & S 1/4 COR SEC 4, T14N, R10W (OLD SURVEY POINT WAS POSSIBLY SET AS CENTER OF SECTION 4) 2" X 3" IRON, 18" DEEP BY PILE ROCKS & WOOD STAKE", AND WITNESSED:

Table with 2 columns: Bearing, Distance. Rows: DUE NORTH FE LINE 24.9, S-67°-E 20" MAPLE 39.90, S-63°-W 21" MAPLE 55.97, N-62°-W TEL. POLE 52.74

Grid table with columns A-M and rows 1-13. Cell (1, F) contains a dot.

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp CHAIRMAN DATE NOV. 18, 1993

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SET REMONUMENTATION CAP IN SURFACE OF CONCRETE BRIDGE DECK, ON LINE BETWEEN F-13 AND G-13, T15N-R10W, AND 183.56 FEET EAST OF F-13, AND IN LINE WITH 215TH AVENUE (20' GRAVEL) EXTENDED FROM THE SOUTH.

WEST END OF CONCRETE BRIDGE DECK WEST 25.7 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-01, NORTH 1/4 CORNER SECTION 4, T14N-R10W. SET REMONUMENTATION CAP IN SURFACE OF CONCRETE BRIDGE DECK, ON LINE BETWEEN F-13 AND G-13, T15N-R10W, AND 183.56 FEET EAST OF F-13, AND IN LINE WITH 215TH AVENUE (20' GRAVEL) EXTENDED FROM THE SOUTH, AND WITNESSED:

- SET 60d SPIKE W/REMONUMENTATION TAG IN SOUTH SIDE GUARD RAIL POST AZ. 89° 169.56 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN NORTH SIDE GUARD RAIL POST AZ. 109° 211.30 FEET
SOUTH 1/4 CORNER SECTION 33, T15N-R10W (COUNTY MONUMENT) AZ. 276° 183.56 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN EAST SIDE GUARD RAIL POST AZ. 232° 39.59 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN SOUTH SIDE GUARD RAIL POST AZ. 298° 64.84 FEET

Signed by James G. Knapp Surveyor's Michigan License No. 25853

Date NOVEMBER 15, 1999

