

**SURVEY & REMONUMENTATION**

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

SEP 12 1996

CORNER APPROVED BY PEER GROUP ON April 15, 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

For corners in Mecosta (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey SEC 33 T 14N R 10W G-12  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

'96 AUG 21 A10:32

*Joann Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, James J. Keller, in a field survey on January, 15 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

February 25, 1838, Abner E. VanNess GLO "Qr. Section Corner in Swamp" 6" dia. Ash

November 3, 1975, Douglas W. Booth #7966 MSHD "Found 3"x3" Wood Stake and 3/8" Iron by Fence Corner" (LCRC Liber 1, Page 246)  
 12" White Pine S50°W 21.43'  
 8" White Pine N40°W 14.59'  
 10" White Pine S40°E 31.77'

June 1994, William G. Tingley #30104 "Found 3/8" Iron by above Witnesses" (Not Rewitnessed)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


January 15, 1996, James J. Keller #10693 Found 1/2" Iron Flush and Wood Stake in Swamp.  
 Found 30d and MSHD Tag W. Sd. 8" White Pine N43°W 14.61'  
 Set 60d E. Sd. 12" White Pine N23°E 46.47'  
 Found 16d and MSHD Tag N.E. Sd. 11" White Pine S36°E 31.63'  
 Found 8d and MSHD Tag N.W. Sd. 12" White Pine S54°W 21.41'

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990

*James H. Knapp*  
CHAIRMAN  
DATE APRIL 15, 1996

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 Set Remonumentation Monument and is accepted as careful and faithful perpetuation of the position of the Original Corner.

- Set 60d & Tag SW Side 8" W.Pine N38°W - 14.50'
- Set 60d & Tag E Side 12" W.Pine N22°E - 46.54'
- Set 60d & Tag NE Side 10" W.Pine S38°E - 31.65'
- Set 60d & Tag NW Side 10" W.Pine S51°W - 21.42'



Signed by *James J. Keller* Date July 1, 1996

Surveyor's Michigan License No. 10693

112

July 2 - 1993

