

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

**CORNER APPROVED BY PEER GROUP ON NOVEMBER 7, 1994**

**SURVEY & LAND CORNER RECORDATION CERTIFICATE**  
**REMONUMENTATION**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF MECOSTA  
 REGISTER OF DEEDS

of corners in

MECOSTA  
 (County)

APR 10 1995  
 Located In:

Corner Code #

'94 NOV 23 AM 11:06

COMMISSION

Public Land Survey T 14 N R 10 W \_\_\_\_\_ M-2 \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Carol Waldron*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

JAMES G. KNAPP, in a field survey on OCTOBER 12, 1994,  
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

**NOTE: ONLY ONE CORNER MAY BE RECORDED ON THIS CERTIFICATE.**

Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST ON SEPT. 4, 1837. CORNER POST PLACED 40.00 CHAINS (2640.00 FEET)  
 FROM S.E. CORNER SECTION 1 AND WITNESSED: BEECH 14" N34°W, 38 LINKS (25.08 FEET)  
 IRONWOOD 6" S32°W, 28 LINKS (18.48 FEET)  
 G.L.O. NOTES STREAM 08 LKS. COURSE W. AT 15.00 CHAINS (990.00 FEET) AND, ANOTHER STREAM 08 LKS, COURSE W. AT 28.32  
 CHAINS (1869.12 FEET) AND 1/4 POST AT 40.00 CHAINS (2640.00 FEET).

GERALD J. GRAY P.S. 17741, NOTED CORNER AS "SET 1/2" IRON ROD", ON A SURVEY IN SECTION 1, T14N-R10W ON JUNE 26, 1978.  
 CORNER RECORDED AS PER P.A. 74, 1970, BY DUANE F. WOODS, P.S. 24625, ON JUNE 29, 1988, IN LIBER 2, PAGE 226,  
 AND NOTED AS, "SET 1/2" STEEL BAR AT FENCE INTERSECTION", AND WITNESSED:

8" MAPLE S05°E, 32.0  
 8" MAPLE N55°E, 13.7  
 16" WILLOW WEST 28.2

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-BAR W/R.L.S. CAP No. 17741 IN REMAINS OF FENCE CORNER (N-S AND W).  
 CORNER IS 1658 FEET NORTH OF 36" CULVERT (G.L.O. NOTED 1650 FEET) AND 829 FEET NORTH OF 6 FOOT WIDE STREAM.  
 (G.L.O. NOTED 770.88 FEET).


APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 343 of 1990

*James G. Knapp*  
 CHAIRMAN  
 DATE Nov. 7, 1994

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 - 1/4 COMMON TO SECTION 1, T14N-R10W, AND SECTION 6, T14N-R9W  
 FOUND 1/2" RE-BAR AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.  
 REMOVED 1/2" RE-BAR AND SET IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, WHICH  
 IS PROTRUDING 3" ABOVE GROUND SURFACE.  
 SET 60d SPIKE W/REMONUMENTATION WITNESS TAG IN W. SIDE 14" MAPLE (W/REMAINS OF N-S FENCE) AZ.182°, 38.52 FEET  
 SET 60d SPIKE W/REMONUMENTATION WITNESS TAG IN S. SIDE 22" ASH (W/ REMAINS OF E-W FENCE). AZ.270°, 28.32 FEET  
 SET 60d SPIKE W/REMONUMENTATION WITNESS TAG IN S.W. SIDE 6" MAPLE AZ.312°, 47.43 FEET  
 SET 60d SPIKE W/REMONUMENTATION WITNESS TAG IN E. SIDE 12" TWIN ASH AZ.352°, 34.53 FEET

signed by *James G. Knapp*  
 Surveyor's Michigan License No. 25853



NOVEMBER 21, 1994

LIBER 100 PAGE 17