

SURVEY & REMONUMENTATION

MECOSTA COUNTY REMONUMENTATION PROGRAM

MAY 16 1996

CORNER APPROVED BY PEER GROUP ON NOVEMBER 28, 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

For corners in
MECOSTA
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 14N R 10W _____ M-9 _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4 Lot No. _____ Recorded Plat _____

5. Private Claims _____

'96 MAY -2 P12:06

Joan Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, JAMES G. KNAPP, in a field survey on OCTOBER 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	6	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
DEPUTY SURVEYOR, ABNER E. VANNESS, SET POST IN JAN. 1838, CORNER POST PLACED 40.00 CHAINS (2640 FEET) FROM 1/4 CORNER COMMON TO SECTIONS 25 AND 30 AND WITNESSED: MAPLE 12" S63°W 32 LINKS (21.12 FEET)
BEECH 12" N75°W 21 LINKS (13.86 FEET)

ROAD SURVEY NOTES AT THE MECOSTA COUNTY ROAD COMMISSION (DRAWING NO. 110-3) BY W. H. WRIGHT, COUNTY ENGINEER, FROM ABOUT 1935, CALL FOR CORNER AS, "SEC. COR. IRON STK."

CORNER RECORDED IN LIBER 1, PAGE 451, AS PER P.A. 74 OF 1970, BY JOHN I. NELSON, P.S. 21273, ON SEPT. 20 1978, AND NOTED AS "FOUND 1" SQUARE HEAD BOLT", AND WITNESSED: 30" MAPLE AZ. 75°, 58.21'
12" MAPLE AZ. 127°, 102.79'
24" MAPLE AZ. 210°, 65.57'
12" MAPLE AZ. 293°, 89.52'

CORNER CALLED FOR AS PER P.A. 132 OF 1970, BY JOHN I. NELSON, P.S. 21273, IN LIBER 10, PAGE 636, AS "FOUND 1" SQUARE HEAD BOLT".

CORNER CALLED FOR AS PER P.A. 132 OF 1970, BY GERALD J. GRAY, P.S. 17741, IN LIBER 10, PAGE 901, ON SEPT. 25, 1980, AS "FND 1" SQ. HEAD BOLT", AND WITNESSED: N75°E 58.21' 30" MAPLE
S53°E, 102.79' 12" TRIPLE MAPLE
S30°W, 65.57' 24" MAPLE

CORNER CALLED FOR AS PER P.A. 132 OF 1970, BY WILLIAM G. TINGLEY, P.S. 30104, IN LIBER 10, PAGE 901, ON SEPT. 29, 1994. APPROVED BY MECOSTA COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345 OF 1990


James M. Knapp
CHAIRMAN
Nov. 28, 1994

B Description of corner evidence found and /or method applied in restoring or reestablishing:
FOUND 1" SQUARE HEAD X 3' LONG BOLT, INSIDE OF VITRIFIED TILE, BURIED 3" BELOW BITUMINOUS ROAD SURFACE, CORNER IS 1.5' WEST OF CENTERLINE OF 180TH. AVENUE, (24' BITUMINOUS) AND AT INTERSECTION WITH 8 MILE ROAD, IN LINE WITH CENTERLINE - WEST, (22' BITUMINOUS), AND 8' NORTH OF CENTERLINE - EAST, (22' BITUMINOUS).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-9 - SECTION CORNER COMMON TO SECTIONS 24 AND 25, T14N-R10W, AND SECTIONS 19 AND 30, T14N-R09W
FOUND 1" SQUARE HEAD X 3' LONG BOLT, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

REMOVED THE 1" SQUARE HEAD X 3' LONG BOLT, AND SET IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AND A HIGHWAY MONUMENT BOX.

SET 60" SPIKE W/REMONUMENTATION TAG IN SOUTH SIDE OF 38" MAPLE AZ. 83°, 58.21 FEET (O.B.T.)
SET 60" SPIKE W/REMONUMENTATION TAG IN S.W. SIDE OF 28" MAPLE AZ. 130°, 102.71 FEET
SET 60" SPIKE W/REMONUMENTATION TAG IN N.W. SIDE OF 38" MAPLE AZ. 212°, 65.70 FEET (O.B.T.)
SET 60" SPIKE W/REMONUMENTATION TAG IN NORTH SIDE OF 18" MAPLE AZ. 288°, 108.11 FEET



James G. Knapp

Date MAY 1, 1996

Surveyor License No. 25853

LIBER 100 PAGE 88

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1977
REVISED MAY 14, 1978
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1992