

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

**CORNER APPROVED BY PEER GROUP ON NOVEMBER 14, 1997**

STATE OF MICHIGAN  
 COUNTY OF MECOSTA  
 RECEIVED FOR RECORD

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

'97 DEC 22 A8:43

For corners in  
MECOSTA  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 14N R 07W C-13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*James G. Knapp*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, JAMES G. KNAPP, in a field survey on JUNE 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Only one corner may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, JOHN HODGSON, SET POST ON JUNE 19, 1839. CORNER POST PLACED 40.00 CHAINS (2640 FEET) FROM SOUTH 1/4 CORNER SECTION 32, AND WITNESSED: ELM 8" N08°W 33 LINKS (21.78 FEET)  
 MAPLE 8" N41°E 27 LINKS (17.82 FEET)

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY GERALD J. GRAY, P.S. 17741, ON JULY 19, 1995, AND RECORDED IN LIBER 11, PAGE 941 AND 942, AND NOTES CORNER AS, "FOUND 1/2" IRON ROD", AND WITNESSED:

NAIL IN P. POLE S60°E 32.00'  
 STOP SIGN N45°E 37.05'  
 NAIL IN 4" MAPLE N78°W 85.35'  
 TWP. SIGN POST S50°W 48.22'

**SURVEY & REMONUMENTATION**

FEB 26 1998

**SECTION**

APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 of 1990

*James G. Knapp*  
 CHAIRMAN  
 DATE NOV. 14, 1997

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

COULD FIND NO EVIDENCE OF ANY PREVIOUS CORNER, SET A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AT THE CALLED FOR FALLING DISTANCE (25 LINKS = 16.50 FEET) EAST FROM THE CLOSING CORNER C-01, AND ON LINE WITH CORNER D-01, T13N-R07W.

CORNER IS 4' EAST OF CENTERLINE OF 50TH. AVENUE (21' BITUMINOUS), AND IN LINE WITH CENTER OF 6 MILE ROAD (18' GRAVEL) EAST AND WEST.

WITNESSES FROM LIBER 11, PAGE 941, WOULD BE AT AZ. 155°, 13.6 FEET FROM REMONUMENTED LOCATION.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-13 - CORNER COMMON TO SECTIONS 31 AND 32, T14N-R07W.  
 SET A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AT THE CALLED FOR FALLING FROM CORNER C-01, T13N-R07W, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF UTILITY POLE AZ. 41°, 53.21 FEET  
 SET 60d SPIKE W/REMONUMENTATION TAG IN S.W. SIDE OF UTILITY POLE AZ. 126°, 45.63 FEET  
 SET 60d SPIKE W/REMONUMENTATION TAG IN N.W. SIDE OF 12" ASH AZ. 222°, 67.68 FEET  
 CORNER C-01, T13N-R07W (MECOSTA COUNTY REMONUMENTATION MONUMENT) AZ. 270°, 16.50 FEET  
 SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF 10" WHITE BIRCH AZ. 313°, 75.20 FEET

Signed by *James G. Knapp* Date OCTOBER 5, 1997  
 Surveyor's Michigan License No. 25853

FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN. 1983  
 ADAPTED FOR WORD PROCESSING, MARCH, 1993

