

MECOSTA COUNTY REMONUMENTATION PROGRAM

OCT 2 1999

CORNER APPROVED BY PEER GROUP ON FEBRUARY 13, 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

SECTION

For corners in

MECOSTA (County)

Located In:

Corner Code #

'99 AUG 27 A9:26

James Brown REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Table with 3 columns: Property Type, Located In (S/T), and Corner Code # (R). Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4 Lot No. Recorded Plat
5 Private Claims

I, JAMES G. KNAPP, in a field survey on MAY 7, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 and a central dot in row 9, column C.

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN 2nd QUARTER 1839, CORNER POST PLACED 39.99 CHAINS (2639.34 FEET) FROM N.E. AND N.W. CORNER COMMON TO SECTIONS 29, AND WITNESSED: BEECH 8" S76°W 11 LINKS (7.26 FEET) MAPLE 10" N33°W 17 LINKS (11.22 FEET)

* CORNER RECORDED AS PER P.A. 74, BY GERALD J. GRAY, P.S. 17741, ON JAN. 25, 1995, IN LIBER 3, PAGE 6. CORNER NOTED AS, "SET BAR AND CAP BY DOUDLING 1/8 CORNER TO EAST AND N.E. SECTION CORNER, IRON FALLS IN NORTH ROAD DITCH", AND WITNESSED: 221 AZ, 51.69' 22" COTTONWOOD 181 AZ, 38.23' 6" ELM 164 AZ, 35.20' "X" ON TOP LARGE STONE 92 AZ, 121.00' NOTCH IN 12" C.M.P.

* THIS LAND CORNER RECORDATION CERTIFICATE DOESN'T APPLY TO THIS CORNER.

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 348 of 1990

James G. Knapp CHAIRMAN DATE FEB. 13, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" X 6" 18" +/- POINTED STONE, BURIED 8" BELOW GRAVEL ROAD SURFACE, UNDER STONE FOUND 1" O.D. IRON PIPE W/CROCKERY AND SURROUNDED WITH STONES, 4' SOUTH OF CENTER OF 8 MILE ROAD (20' GRAVEL), AND IN LINE WITH TREE ROW - SOUTH.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-09 - 1/4 CORNER COMMON TO SECTIONS 20, AND 29, T14N-R07W. FOUND 4" X 6" 18" +/- POINTED STONE, BURIED 8" BELOW GRAVEL ROAD SURFACE, UNDER STONE FOUND 1" O.D. IRON PIPE W/CROCKERY AND SURROUNDED WITH STONES, 4' SOUTH OF CENTER OF 8 MILE ROAD (20' GRAVEL), AND IN LINE WITH TREE ROW - SOUTH AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, OVER THE 1" IRON PIPE, WITH THE STONE ALONG SIDE, AND WITNESSED: SOUTH END OF 12" CSP CULVERT AZ. 95°, 176.02 FEET FOUND SPIKE W/TAG No. 30104 TAG IN EAST SIDE OF UTILITY POLE AZ. 177°, 21.81 FEET SET 60d SPIKE W/REMONUMENTATION TAG IN N.W. SIDE OF 14" WILD CHERRY AZ. 242°, 42.96 FEET SET 60d SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF UTILITY POLE AZ. 350°, 38.91 FEET

Signed by James G. Knapp Surveyor's Michigan License No. 25853

Date AUGUST 24, 1999

LIBER 101 PAGE 156



APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 2007 REVISED MAY 1998 REGISTERED LAND SURVEYORS