

SURVEY & REMONUMENTATION

MECOSTA COUNTY REMONUMENTATION PROGRAM

OCT 26 1999

CORNER APPROVED BY PEER GROUP ON FEBRUARY 13, 1998

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'99 JUN -1 P3:45

For corners in

MECOSTA
(County)

Located In:

Corner Code #

1. Public Land Survey	T 14N R 08W	C-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Joann Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4 Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on DECEMBER 8, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST IN JUNE 1837, CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM SOUTH 1/4 CORNER SECTION 32, AND WITNESSED: BEECH 12" N46°W 36 LINKS (23.76 FEET)
BEECH 8" N36°E 20 LINKS (13.20 FEET)

CORNER NOTED IN P.A. 132 SURVEY AS RECORDED IN LIBER 11, PAGES 638 - 639, BY JAMES J. KELLER, P.S. 10693, ON MAY 5, 1993, AS, "1/2" REBAR WEST 11.88' FROM N.E. CORNER SECTION 6, T13N-R08W".

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James H. Knapp
CHAIRMAN
DATE FEB. 13, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-BAR, 3" BELOW GRAVEL ROAD SURFACE, 7' WEST OF CENTER OF (22' GRAVEL), AND IN LINE WITH 12 MILE ROAD (10' TRAIL - WEST AND 12' NORTH OF 10' TRAIL - EAST) AND BEING 473' NORTH OF LEFT BANK OF SHINGLE BOLT CREEK.

SET MONUMENT AND HIGHWAY MONUMENT BOX DURING BITUMINOUS PAVING ON MAY 6, 1998, CORNER IS NOW 6.9' WEST OF CENTERLINE OF 110TH. AVENUE (21' BITUMINOUS).

MEASURED DISTANCE TO C-02, T13N-R08W = 2643.11', AND TO C-11, T14N-R08W = 5142.73'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C - 13, CORNER COMMON TO SECTIONS 31 AND 32, T14N-R08W.
FOUND 1/2" REBAR, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. REMOVED THE 1/2" REBAR, AND PLACED IN THE SAME POSITION A-STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:
FOUND NAIL WITH TAG NO. 30104 IN N.W. SIDE OF 10" ELM AZ. 48°, 55.25 FEET
1/2" REBAR (SECTION CORNER 5 AND 6, T13N-R08W) AZ. 90°, 11.88 FEET
FOUND NAIL WITH TAG NO. 30104 IN S.E. SIDE OF 14" MAPLE AZ. 242°, 57.72 FEET
FOUND NAIL WITH TAG NO. 30104 IN N.E. SIDE OF 6" MAPLE AZ. 328°, 49.05 FEET

Signed by *James H. Knapp*
Surveyor's Michigan License No. 25853

Date NOVEMBER 16, 1998

