

REMONUMENTATION

MECOSTA COUNTY REMONUMENTATION PROGRAM

NOV 18 1997

CORNER APPROVED BY PEER GROUP ON DECEMBER 13, 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>MECOSTA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 14N R 08W	G-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4 Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

'97 NOV -7 P2:24

Jessie Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JACK E. PIERSON, in a field survey on OCTOBER 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST ON NORTH LINE 10 LINKS EAST OF POST, ON DECEMBER 5, 1838, AND WITNESSED:
18" BEECH S53°W 26 LINKS
15" PINE S04°E 30 LINKS

COUNTY SURVEYOR RECORD BOOK NO. 1, PAGE 58 AT REGISTER OF DEEDS OFFICE SHOW NOTES BY L.W. JUNE, COUNTY SURVEYOR, ON MAY 5, 6, 7, 1898, CORNER NOTED AS, "TILE CORNER 10 L. WEST OF COR. FOR 3 & 4".

ROAD SURVEY NOTES AT THE MECOSTA COUNTY ROAD COMMISSION BY E. E. SOURS, COUNTY ENGINEER, DATED APRIL 20, 1927, TO BE AT STATION 51+208 FROM CORNER COMMON TO SECTIONS 3, 4, 9, AND 10, AND BEING "TILE - 10 L. W. OF COR. FOR 3 & 4".

CORNER USED BY JERRY TAYLOR, P.S. 32342 AND WITNESSES:

18" W. PINE	N25°E,	67.05 FEET
20" W. PINE	S65°E,	30.4 FEET
2" W. PINE	S40°W,	54.2 FEET
32" W. PINE	N50°W,	67.6 FEET

CORNER USED BY WILLIAM TINGLEY, P.S. 30104

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James M. Knapp
CHAIRMAN
DATE DEC. 13, 1996

B Description of corner evidence found and/or method applied in restoring or reestablishing corner

ON JUNE 6, 1997, FOUND R.R. SPIKE ON APPROXIMATE CENTERLINE OF 90TH. AVENUE. LOCATION IS IN FILL AREA. EXCAVATION UNCOVERED NO OTHER MONUMENT EVIDENCE. POSITION AGREE WITH JUNE'S DISTANCES TO 1/4 COR. POSITION - EAST. CORNER POSITION HAS BEEN USED BY OTHER SURVEYORS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 - SECTION CORNER COMMON TO SECTIONS 3 AND 4, T14N-R08W
FOUND RAILROAD SPIKE AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

REMOVED THE RAILROAD SPIKE AND SET IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AND HIGHWAY MONUMENT BOX.

24" WHITE PINE	AZ. 113°,	30.57 FEET
10" RED PINE	AZ. 153°,	82.17 FEET
24" WHITE PINE	AZ. 32°,	67.18 FEET
S.W. CORNER SECTION 34, T15N-R08W (MECOSTA COUNTY REMONUMENTATION MONUMENT)	AZ. 270°,	6.84 FEET

Signed by *Jack E. Pierson*
Surveyor's Michigan License No. 19305

Date AUGUST 19, 1997

