

MECOSTA COUNTY REMONUMENTATION PROGRAM

NOV 18 1997

CORNER APPROVED BY PEER GROUP ON DECEMBER 13, 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MECOSTA
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 14N | R | 08W | I-01 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

'97 NOV -7 P2:24

Jeanne Brown
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JACK E. PIERSON, in a field survey on OCTOBER 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ON DECEMBER 5, 1838, DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST 33 LINKS WEST OF POST TO SECTIONS 34 AND 35, T15N-R08W, AND WITNESSED: 8" BEECH S66°W 67 LINKS
12" MAPLE S29°E 11 LINKS

FROM COUNTY SURVEYOR'S RECORD BOOK NO. 1, PAGE 58, DATED MAY 5, 6, 7, 1899, LYMAN JUNE, "OLD TILE 33 LINKS EAST OF CORNER FOR 2 AND 3.

CORNER CALLED FOR IN CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY GERALD GRAY, P.S. 17741, ON JUNE 9, 1977, AND RECORDED IN LIBER 10, PAGE 408, AND NOTED AS, "FOUND IRON", AND WITNESSED: S50°W 41.93' P. POLE
WEST 30.23' F. POST
(MISTAKENLY CALLS FOR THE S.E. CORNER OF SECTION 34, T15N-R08W AS THE, "N.E. CORNER OF SECTION 3, T14N-R08W").

CORNER RECORDED AS PER P.A. 74 OF 1970, BY GERALD GRAY, P.S. 17741, IN LIBER 1, PAGE 328, ON SEPT. 1, 1977, AS, "FOUND IRON", AND WITNESSED: P. POLE S50°W 41.93'
F. POST WEST 30.23'
(MISTAKENLY RECITES THE SAME INFORMATION ON THIS CORNER AS GIVEN ON THE SURVEY RECORDED IN LIBER 10, PAGE 408).



APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1996

James H. Knapp
CHAIRMAN
DATE DEC. 13, 1996

B Description of corner evidence found and /or method applied in restoring or reestablishing corner

NO DIRECT CORNER WAS FOUND. CORNER WAS POSITIONED BETWEEN THE S. 1/4 CORNER AND THE S.E. CORNER OF SECTION 34, T15N-R08W CONFORMING TO THE DISTANCES CONFIRMED FROM THE L. W. JUNE SURVEY OF MAY, 1899.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-01 - CORNER COMMON TO SECTION 2, AND 3, T14N-R08W
SET STANDARD COUNTY REMONUMENTATION MONUMENT AT THE RECORD DISTANCE, (LYMAN JUNE, MAY 1899) FROM THE TWO ADJACENT STANDARD CORNERS AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER, AND WITNESSED:

- | | | |
|--|-----------|------------|
| N.E. CORNER OF OUTBUILDING | AZ. 252°, | 95.37 FEET |
| P. POLE | AZ 212°, | 26.68 FEET |
| 8" ASPEN | AZ 51°, | 63.74 FEET |
| 3" APPLE | AZ 126°, | 61.23 FEET |
| N.E. CORNER SECTION 3, T14N-R08W (MECOSTA COUNTY REMONUMENTATION MONUMENT) | AZ 90°, | 21.78 FEET |

Signed by *Jack E. Pierson* Date OCTOBER 10, 1997

Surveyor's Michigan License No. 19305 LIBER 100 PAGE 303