

SURVEY &  
REMONUMENTATION

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

MAY 05 1997

CORNER APPROVED BY PEER GROUP ON SEPTEMBER 26, 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

For corners in  
MECOSTA  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 15N R 09W  
T 15N R 10W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

A-07 ✓  
M-7  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

2. Property Controlling  
in Section

3. Miscellaneous  
Property in Sec.

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

'96 DEC 17 AM 11:31

*Joan Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, JAMES G. KNAPP, in a field survey on AUGUST 8, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST ON SEPT. 25, 1837. CORNER POST PLACED 40.00 Chains (2640 Feet) FROM 1/4 CORNER COMMON TO SECTION 19 AND 24, AND BEING 0.10 CHAINS (6.60 FEET) SOUTH OF A 10 LINKS STREAM AND WITNESSED:  
BEECH 10" S26°W 31 Links (20.46 Feet)  
ELM 20" N9°W 34 Links (22.44 Feet)

IN 1895, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE COLFAX TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R09W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 281 AND 282. CORNER IS NOTED AS "ORGNL, - REC'D BY ALL".

IN OCT. 1895, L. W. JUNE, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK No. 1, PAGE 10, NOTED CORNER AS "TILE COR." AND BEING 33.96 CHAINS (2241.36 FEET) FROM THE 1/4 CORNER COMMON TO SECTION 18 AND 19, T15N-R09W.

IN JUNE, 1896, L. W. JUNE, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK No. 1, PAGE 17, NOTED CORNER AS "TILE COR." AND BEING 33.96 CHAINS (2241.36 FEET) FROM THE 1/4 CORNER COMMON TO SECTION 18 AND 19, T15N-R09W, AND 39.83 CHAINS (2628.78 FEET) FROM 1/4 CORNER COMMON TO SECTION 13 AND 18, AND BEING 7.16 CHAINS (472.56 FEET) SOUTH OF P.I. IN ROADWAY.

IN APRIL 1964, GEORGE BLASS, P.S. 5489, ON JOB NO. 951-64 NOTES SECTION CORNER AS BEING 478.43 FEET SOUTH OF P.I.

CORNER NOTED IN P.A. 132 SURVEY AS RECORDED IN LIBER 10, PAGE 156, BY CLINTON E. COLE, P.S. 17645, ON AUG. 27, 1973, WITH A DISTANCE OF 1314.28 FEET FROM SECTION CORNER TO SOUTH 1/8 CORNER ON WEST LINE SECTION 18.

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990

*James G. Knapp*  
CHAIRMAN  
DATE SEPT. 26, 1996


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" IRON ROD INSIDE OF A 3" X 9" VITRIFIED CLAY TILE, BURIED 2" BELOW GROUND SURFACE, AND 3' EAST OF A NORTH AND SOUTH FENCE (114 FEET SOUTH OF FENCE CORNER), AND 8 FOOT +/- SOUTH OF A 5 FOOT +/- STREAM. ALSO BEING 477.64 FEET SOUTH OF P.I. OF M-20, AND BEING 2,238.90 FEET FROM THE 1/4 CORNER COMMON TO SECTION 18 AND 19, T15N-R09W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-07 - SECTION CORNER COMMON TO SECTION 18, AND 19, T15N-R09W, AND SECTION 13, AND 24, T15N-R10W. FOUND A 1/2" IRON ROD INSIDE OF A 3" VITRIFIED CLAY TILE IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE 1/2" IRON ROD AND INSIDE OF A 3" VITRIFIED CLAY TILE

CONCRETE MONUMNET	AZ.	01°,	94.39 FEET
SET 60p SPIKE W/REMONUMENTATION TAG IN WEST	AZ.	10°,	166.37 FEET
SET 60p SPIKE W/REMONUMENTATION TAG IN EAST	AZ.	185°,	115.66 FEET
SET 60p SPIKE W/REMONUMENTATION TAG IN SOUTHWEST	AZ.	336°,	60.35 FEET
SOUTHEAST CORNER OF CONCRETE BLOCK BUILDING	AZ.	352°,	194.60 FEET



Signed by James G. Knapp Date AUGUST 8, 1996  
Surveyor's Michigan License No. 25853

FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS  
REVISED MAY 14, 1975  
REVISED JAN. 1993  
ADAPTED FOR WORD PROCESSING MARCH, 1993