

**SURVEY &
REMONUMENTATION**

MECOSTA COUNTY REMONUMENTATION PROGRAM

APR 04 1996

CORNER APPROVED BY PEER GROUP ON NOVEMBER 18, 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN
COUNTY OF MECOSTA
Filing Requirement of Act 74, Mich. P.A. 1970 RECEIVED FOR RECORD

For corners in
MECOSTA
(County)

Located In: Corner Code #

Public Land Survey T 15N R 09W E-13

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4 Lot No. _____ Recorded Plat _____

5. Private Claims _____

95 DEC 19 P1:51

James Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on OCTOBER 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, NOTED "PINE 16" FOR CORNER SECTION 32 AND 33", IN SEPT. 1837, ON SOUTH TOWNSHIP BOUNDARY. CORNER PLACED 40.00 CHAINS (2640.00 FEET) FROM S. 1/4 CORNER SECTION 33.

IN 1895, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE COLFAX TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R09W, AS RECORDED IN COUNTY SURVEYOR'S RECORD BOOK No. 1, PAGES 281 AND 282. NOTES SHOW, "PINE STUMP 20", S45°W 44 = REWITNESS OLD CORNER TREE FOUND DOWN".

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, BY E. E. SOURS IN JULY. 1919, SHOW SECTION CORNER AND WITNESSED:

RED OAK 20" S11°W, 32.9 FEET
W. OAK 14" S44°-15'W, 69.2 FEET
R. OAK 10" N43°-45'E, 59.0 FEET

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, BY H. F. ANDERSON IN SEPT. 1921 ON 160TH. AVENUE BEGAN 310 FEET NORTH OF CORNER 32 AND 33.

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
CHAIRMAN
DATE NOV. 18, 1993

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD, INSIDE 3" VITRIFIED TILE, BURIED 6.2' BELOW SURFACE IN ROAD FILL SECTION, IN CENTERLINE OF 12 MILE ROAD (22' GRAVEL).

FOUND 5/8" REBAR AS RECORDED IN LIBER 2, PAGE 53, BY JOHN I. NELSON, P.S. 21271, AT AZ 266°, 27.4 FEET.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E - 13 SECTION CORNER COMMON TO SECTIONS 32 AND 33, T15N-R9W
FOUND 1/2" IRON ROD INSIDE OF 3" VITRIFIED TILE AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION POSITION OF THE ORIGINAL CORNER.
THE 1/2" IRON ROD AND 3" VITRIFIED TILE WAS LEFT AS FOUND, AND A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, BURIED 8" BELOW ROAD SURFACE, WAS PLACED ABOVE THEM.
SET 60p SPIKE W/REMONUMENTATION WITNESS TAG IN N.W. SIDE OF 12" WHITE PINE AZ. 58°, 90.88 FEET
SET 60p SPIKE W/REMONUMENTATION WITNESS TAG IN N.E. SIDE OF 18" MAPLE AZ. 132°, 39.45 FEET
SET 60p SPIKE W/REMONUMENTATION WITNESS TAG IN EAST SIDE OF 24" TRIPLE RED OAK AZ. 191°, 32.73 FEET
SET 60p SPIKE W/REMONUMENTATION WITNESS TAG IN NORTH SIDE OF 28" BEECH AZ. 262°, 103.18 FEET



Signed by James G. Knapp Date DECEMBER 10, 1995
Surveyor's Michigan License No. 25853