

SURVEY & REMONUMENTATION

MECOSTA COUNTY REMONUMENTATION PROGRAM

MAR 14 2000

CORNER APPROVED BY PEER GROUP ON April 17, 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

SECTION
For Corners in

'99 DEC 14 P2:23

Mecosta (County)	Located In:		Corner Code #
	T 15N	R 9W	I-07
	T	RR	
	T	R	
1. Public Land Survey	T	R	
	T	R	
S	T	R	
S	T	R	
S	T	R	
S	T	R	

Joann Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

I, James H. Carter, in a field survey on November, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of court law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of Michigan Board of Land Surveyors or by a decree of a court of law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	4	5	6	7	8	9	10	11	12			
3												
4	7	8	9	10	11	12						
5												
6	13	14	15	16	17	18	19	20	21	22	23	24
7												
8	19	20	21	22	23	24						
9												
10	25	26	27	28	29	30	31	32	33	34	35	36
11												
12	31	32	33	34	35	36						
13												

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838 - JAN- FEB, DEPUTY SURVEYOR, A. E. VAN NESS, SET POST COMMON TO SECTIONS 14,15,22,& 23. 10" TAMARACK - N 59 E - 62 LINKS, 8" TAMARACK - N 62 W - 38 LINKS
- 1895 - L. W. JUNE - ORIGINAL STAKE IN STONE HEAP.
- 1905 L. W. JUNE - TILE CORNER.
- 19?? - P. M. RAILROAD, TIE TO TILE, 421.2 FT FROM CENTERLINE.
- 1996 - MID - MICHIGAN, USED CALCULATED POSITION, JUNE'S RECORD DISTANCE FROM N 1/4 COR SEC 22 ON C/L 15 MI. ROAD EXTENDED.

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James S. Knapp
CHAIRMAN
DATE April 17, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

LOCATED STONE HEAP UNDER 3.5' OF WATER, STRONG MAGNETIC PULL IN CENTER OF STONE HEAP BELIEVED TO BE STEEL ROD IN LYMAN JUNE TILE THAT IS COMMON AMONG OTHER JUNE CORNERS IN SAME AREA. SET MECOSTA COUNTY REMONUMENTATION MONUMENT IN CENTER OF ROCK PILE AND EXTENDING 2 FEET ABOVE WATER SURFACE WHICH MAY VARY FROM TIME TO TIME BECAUSE OF BEAVER DAM. ALSO SET 2 MECOSTA COUNTY REMON MONUMENTS AS POINTS OF REFERENCE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 - CORNER COMMON TO SECTIONS 15, 14, 22 & 23, T15N, R09W. SET A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. CORNER LOCATION IS UNDER WATER, ALSO SET TWO REFERENCE MONUMENTS.

- REF MON SET ON SOUTH LINE SEC 15 @ 1/8 COR POSITION 1299.55' WEST OF I-7.
- N 69 W - 123.01' - NAIL AND TAG IN POWER POLE. N 12 E - 152.62' - 28" TWIN ASH.
- S 59 E - 165.08' - NAIL AND TAG IN POWER POLE. S 56 E - 12.84' - STREET SIGN POST.
- S 06 E - 162.87' - N W COR OF BARN. S 20 W - 141.85' - NAIL & TAG IN 28" MAPLE.

- REF MON SET ON EAST LINE OF SEC 15, 422.70' NORTH OF I-7 AND IN CENTER OF OLD R.R. BED.
- N 51 E - 8.08' - NAIL & TAG IN COR FEN POST. N 84 E - 12.01' - NAIL & TAG IN BRACE FEN POST.
- WEST - 16.31' - NAIL AND TAG IN BEAVER CUT STUMP. N 58 W - 84.38' - NAIL & TAG IN NE LEG OF HUNTING TOWER.



Signed by James H. Carter Date DEC 13, 1999

Surveyor's Michigan License No. 33973