

# MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON 6-12-98  
 LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

STATE OF MICHIGAN  
 COUNTY OF MECOSTA  
 RECEIVED FOR RECORD

Mecosta  
 (County)

Located In:		Corner Code #
T	15N	R 9W 1-09
T		R
T		R
T		R
S	T	R
S	T	R
S	T	R
S	T	R

'98 AUG 19 A9:54

1. Public Land Survey

SURVEY &  
 REMONUMENTATION

*Joan Brown*  
 REGISTER OF DEEDS

OCT 29 1998

2. Property controlling  
 in Section  
 3. Miscellaneous  
 Property in Sec.

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, James H. Carter, in a field survey on May 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of court law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of Michigan Board of Land Surveyors or by a decree of a court of law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		5		6		7		8		9		10	
3													
4		11		12		13		14		15		16	
5													
6		17		18		19		20		21		22	
7													
8		23		24		25		26		27		28	
9													
10		29		30		31		32		33		34	
11													
12		35		36		37		38		39		40	
13													

**NOTE: Only one corner may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1837 - JAN, DEPUTY SURVEYOR, A. E. VAN NESS, SET POST COMMON TO SECTIONS 22-23-26 & 27, BEECH 10" - N 25 E - 25 LINKS, BEECH 8" - N 60 W - 20 LINKS.  
 1895 - L. W. JUNE - OLD STAKE, 36" PINE STUMP - N 40 W - 44 L, 33" PINE STUMP - S 75 W - 26 L.

1989 - LCRC L-2, P-251, DUANE F. WOOD, FOUND STEEL BAR IN CENTERLINE OF ROAD INTERSECTION 10" PINE - S 80 W - 83.55', P. POLE - N 70 E - 102.30', TW CHERRY - S 25 E - 84.00'.

1989 - LCRC L-2, P -276, JOHN E. McLANE FOUND 5/8" REROD IN CENTERLINE OF 140th AVE AND 6' NORTHERLY OF E. BOUND 14 MI. RD. 16" ASH - AZ 22 - 105.67', POWER POLE - AZ 79 - 102.29', MBT RISER BOX - AZ 149 - 48.22', 10" RED PINE - AZ 268 - 83.18'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ROD WITH RLS CAP #28415 (JOHN McLANE) TWO FT. BELOW GRAVEL SURFACE AND ONE HALF FT. SOUTH OF LARGE STONE AND 0.3 FT SOUTH OF AN IRON PIN LYING SIDEWAYS, THE CAPPED REROD HAD TRACES OF TILE BITS LOCATED AROUND IT, UPON FURTHER EXCAVATION SAID ROD WAS FOUND TO BE IN THE CENTER OF A CLAY TILE AS VIEWED BY M.J. MORTON AND J.S. CARTER.

FOUND POWER POLE - N 81 E - 104.58', PINE - WEST - 80.64', PHONE RISER IN SE QUAD APROX 48 FT.


SET MECOSTA COUNTY REMONUMENTATION MONUMENT IN TILE.

APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 of 1990

*James H. Knapp*  
 CHAIRMAN  
 DATE June 12, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

1-9 - CORNER COMMON TO SECTIONS 22, 23, 26 AND 27, T15N, R09W.  
 SET A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AND IS ACCEPTED AS CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.  
 N 77 W - 92.63' - NAIL AND TAG IN 12" ELM  
 WEST - 80.64' - NAIL AND TAG IN 14" RED PINE  
 N 81 E - 104.58' - NAIL AND TAG IN POWER POLE  
 S 41 E - 49.10' - NAIL AND TAG IN FENCE POST



Signed by James H. Carter

Date July 29, 1998

Surveyor's Michigan License No. \_\_\_\_\_

33973

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983