

SURVEY & REMONUMENTATION
MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON MAY 18, 1995

APR 04 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mecosta Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey SEC 15 T 15N R 7W _____ I-5 _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Joanne Brown
 Register of Deeds
 Mecosta County

'95 NOV -2 A11:13

Register of Deeds Stamp & File Number

I, James J. Keller, in a field survey on February 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1839 Noah Brookfield GLO Set Post corner of sections 10-11-14& 15
 B. Beech 10" N40°W 11 Links; Hemlock 20" S81°E 10 Links
 (Book 1 Page 92)
 1895-96 Lyman W. June, Co. Surveyor Set Tile; 6" Birch S35°W 54 Links
 Fence Post East 32 Links
 1898 Lyman W June - Found Tile Corner
 1989 Wood #24625 (L11-P378) Found Iron in clay tile
 Twin Maple N75°E 24.25'
 24" Pine S30W 49.55
 Power Pole N45°W 114.6'

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990

James J. Knapp
 CHAIRMAN
 DATE MAY 18, 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 10 1994, James J. Keller #10693 Found 2" Rail Road Rail 14" long in tile- top tile broken, Rail is 6" deep in nest of stones. At 1.2' encountered another nest of stones. At 2.0' deep encountered remains of wood stake in sand. At 2.4' deep found clay tile with remains of wood stake inside it. Tile was 3" in diameter and 8" long. Nothing was found beneath this final tile.

Left as is.


- Found 40d Distribution pole N45°W 114.46'
- Set 30d and tag 12"-8" Twin Maple Stump N78°E 24.25'
- Set 30d and tag Distribution Pole S45°E 62.34'
- Found 40d and tag 31" White Pine S30°W 49.54'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument and is accepted as a careful and faithful perpetuation of the position of the original corner.

- Found 40d and set tag Distribution pole N45°W 114.46'
- Set 30d and tag 12"-8" Twin Maple Stump N78°E 24.25'
- Set 30d and tag Distribution Pole S45°E 62.34'
- Found 40d and tag 31" White Pine S30°W 49.54'

Signed by James J. Keller Date 27 June 1995
 Surveyor's Michigan License No. 10693



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 29, 1971
 REVISION MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993