

**SURVEY & REMONUMENTATION**

**MAR 14 2000 MECOSTA COUNTY REMONUMENTATION PROGRAM**

**CORNER APPROVED BY PEER GROUP ON FEBRUARY 12, 1999**

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

'99 DEC 14 P2:23

For corners in <u>MECOSTA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>07W</u>	<u>K-01</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*James Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on DECEMBER 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN MAY 1839, CORNER POST PLACED 44.10 CHAINS (2910.60 FEET) FROM 1/4 CORNER, SECTIONS 1 AND 2, AND 64 LINKS (42.24 FEET) EAST OF CORNER 35 AND 36, T16N-R07W, AND WITNESSED:  
BEECH 10" S58°W 7 LINKS (4.62 FEET)  
LYNN 12" S17°E 36 LINKS (23.76 FEET)

IN 1895-6, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE SHERIDAN TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R07W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 288 AND 289 (FROM FIELD BOOK NO. 1, PAGES 67 THRU 75). CORNER NOTED AS, "64 L. E. OF COR. FOR SEC. 35 & 36, ELM 10 S15E 75 - ORIGINAL".

CORNER CALLED FOR IN COUNTY SURVEYOR'S BOOK NO. 1, PAGE 68, (FROM FIELD BOOK NO. 3, PAGES 138 THRU 141), BY L. W. JUNE, COUNTY SURVEYOR, DATED JANUARY 8, 9, AND 10, 1900, AND NOTED AS, "TILE CORNER", AND BEING 39.38 CHAINS (2599.08 FEET) FROM NORTH 1/4 CORNER, AND 44.86 CHAINS (2960.76 FEET) FROM WEST 1/4 CORNER SECTION 1.

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, BY E. E. SOURS, DATED FEB. 1926, NOTES CORNER AS, "TILE CORNER", AND BEING AT STATION 29+59.9, WITH 1/4 CORNER, SECTIONS 1 AND 2, AT STATION 0+00, AND WITNESSED:  
6" ELM S65°W 53.51'  
14" ELM S12 1/2°W 64.4'

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 343 of 1990

*James G. Knapp*  
CHAIRMAN  
DATE FEB. 12, 1999

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1/2" IRON ROD, INSIDE OF 3" VITRIFIED CLAY TILE, 10" BELOW GRAVEL SURFACE, IN CENTER OF 18 MILE ROAD (28' GRAVEL - EAST AND 20' BITUMINOUS - WEST), AND 18' EAST OF 10<sup>TH</sup> AVENUE (24' GRAVEL - SOUTH) AND 36' EAST OF 10<sup>TH</sup> AVENUE (22' GRAVEL - NORTH).

MEASURED DISTANCE TO L-01 = 2603.11 FEET.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-01, CORNER COMMON TO SECTIONS 1, AND 2, T15N-R07W.  
FOUND 1/2" IRON ROD, INSIDE OF 3" VITRIFIED CLAY TILE, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
REMOVED THE 1/2" IRON ROD, INSIDE OF 3" VITRIFIED CLAY TILE, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, AND WITNESSED:  
SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF 12" ELM

- |  |                       |
|--|-----------------------|
| 3" ELM                                   | AZ. 48°, 101.21 FEET  |
| "I" BEAM 6" X 4' HIGH IN FENCE LINE      | AZ. 154°, 132.38 FEET |
| FOUND SPIKE IN EAST SIDE OF UTILITY POLE | AZ. 228°, 66.66 FEET  |
|  | AZ. 310°, 90.12 FEET  |

Signed by James G. Knapp  
Surveyor's Michigan License No. 25853

Date DECEMBER 13, 1999



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS JANUARY 1975  
ADAPTED FOR WORKING SURVEYS BY MICHIGAN STATE BOARD OF SURVEYORS, 1983