

SURVEY & MECOSTA COUNTY REMONUMENTATION PROGRAM
REMONUMENTATION CORNER APPROVED BY PEER GROUP ON DECEMBER 13, 1996

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED FOR RECORD

For corners in MECOSTA
 (County)

Located in:

Corner Code #

'96 DEC 17 A11:32

- | | | | | | |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 15N | R | 08W | B-11 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
- 4 Lot No. _____, Recorded Plat _____
 5. Private Claims _____

James Brown
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, JAMES G. KNAPP, in a field survey on SEPTEMBER 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST ON DEC. 21, 1838, CORNER POST PLACED 40.00 CHAINS (2640 FEET) FROM CORNER COMMON TO SECTIONS 29, 30, 31 AND 32, WITNESSED:
 PINE 20" S62°E 10 LINKS (6.60 FEET)
 PINE 16" S36°W 28 LINKS (18.48 FEET)

IN 1896, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE MARTINY TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R08W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 290 AND 291. CORNER IS WITNESSED AS, PINE STUMP 16" S30°W 28 = O.B.T.,
 PINE STUMP 30" S41°E 21 = O.B.T.

* CORNER RECORDED AS PER P. A. 74 OF 1970, IN LIBER 1, PAGE 380, BY GERALD J. GRAY, P.S. 17741, ON JAN. 25, 1978, AND NOTED AS, "FND. R. R. SPIKE", AND WITNESSED:
 2" OAK N55°W 57.35'
 T. POLE N65°W 53.20'
 3" COTTONWOOD S65°W 42.40'

CORNER RECORDED AS PER P. A. 74 OF 1970, IN LIBER 1, PAGE 519, BY GERALD J. GRAY, P.S. 17741, ON AUG. 14, 1979, AND NOTED AS, "FND. RR SPIKE", AND WITNESSED:
 UTILITY POLE SOUTH 33.57'
 13" POPLAR S25°E 53.00'
 14" POPLAR N25°E 30.48'

APPROVED BY MECOSTA CO. PEER GRP
 IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
 CHAIRMAN
 DATE DEC. 13, 1996

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND R.R. SPIKE 3" BELOW GRAVEL ROAD SURFACE, AND AT 30" BELOW ROAD SURFACE FOUND A 10" X 8" POINTED ROCK ON TOP OF A PILLAR OF ROCKS, AFTER BITUMINOUS PAVING IN OCT. 1996, CORNER IS 1.6' NORTH OF CENTERLINE OF 13 MILE ROAD (20 BITUMINOUS), CORNER IS 34' SOUTH OF FENCE CORNER, (FENCE EAST - WEST & NORTH), AND IN LINE WITH STUMP FENCE ROW - NORTH, AND OCCUPATION ROW - SOUTH, AND 7 FEET EAST OF 15" CSP CULVERT.


* DOESN'T SEEM TO APPLY TO THIS CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 B-11 1/4 CORNER COMMON TO SECTIONS 30 AND 31, T15N-R08W.
 FOUND R.R. SPIKE 3" BELOW GRAVEL ROAD SURFACE, AND AT 30" BELOW ROAD SURFACE FOUND A 10" X 8" POINTED STONE ON TOP OF A COLUMN OF ROCKS AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT INSIDE OF A HIGHWAY MONUMENT BOX OVER THE TOP OF THE COLUMN OF ROCKS:
 SET 60d SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF UTILITY POLE AZ. 2°, 62.26 FEET
 FOUND 20d SPIKE IN EAST SIDE OF 16" POPLAR AZ. 30°, 32.70 FEET O.B.T.
 SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF UTILITY POLE AZ. 182°, 34.10 FEET
 FOUND 20d SPIKE IN N.W. SIDE OF TWIN 14" RED OAK AZ. 240°, 65.26 FEET

Signed by *James G. Knapp*

Date DECEMBER 11, 1996

Surveyor's Michigan License No. 25853



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS
 REVISED MAY 14
 REVISED JAN.
 ADAPTED FOR WORD PROCESSING MARCH