

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

APR 26 1996

CORNER APPROVED BY PEER GROUP ON NOVEMBER 2, 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

'96 APR 17 AIO:53

For corners in MECOSTA Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 15N R 08W D-3  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4 Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Joann Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, JAMES G. KNAPP, in a field survey on OCTOBER 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Only one corner may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN DEC. 1838. CORNER POST PLACED 40.04 CHAINS (2642.64 FEET) FROM SECTION CORNER, 5, 6, 7 and 8 AND WITNESSED:  
PINE 8" S43°E 23 LINKS (15.18 FEET)  
BEECH 11" N18°W 16 LINKS (10.56 FEET)

IN 1896, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE MARTINY TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R8W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 290 AND 291. NOTES SHOW "STAKE 50 L. SOUTH OF COR. - EQUAL MEASURE".



APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 343 of 1990

*James G. Knapp*  
CHAIRMAN  
DATE Nov. 2, 1995

Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUR IRON ROD, BURIED 5" DEEP, 2' NORTH OF CENTERLINE OF 17 MILE. (20' BITUMINOUS) AND IN LINE WITH FENCE ROW (NORTH AND SOUTH).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-3 - 1/4 CORNER COMMON TO SECTIONS 5, and 8, T15N-R08W  
FOUND 1/2" IRON ROD AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. REMOVED THE 1/2" IRON ROD AND SET IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AND A HIGHWAY MONUMENT BOX.

SET 60p SPIKE W/REMONUMENTATION TAG IN EAST	SIDE OF UTILITY POLE	AZ. 06°,	30.75 FEET
SET 60p SPIKE W/REMONUMENTATION TAG IN S.E.	SIDE OF 12" POPLAR	AZ. 52°	50.82 FEET
SET 60p SPIKE W/REMONUMENTATION TAG IN WEST	SIDE OF CORNER FENCE POST	AZ. 182°	33.63 FEET
SET 60p SPIKE W/REMONUMENTATION TAG IN N.W.	SIDE OF 16" WHITE PINE	AZ. 226°	71.78 FEET

Signed by *James G. Knapp* Date APRIL, 15 1996  
Surveyor's Michigan License No. 25853