

OCT 29 1998

CORNER APPROVED BY PEER GROUP ON OCTOBER 10, 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

SECTION

For corners in

MECOSTA (County)

Located in:

Corner Code #

- 1. Public Land Survey T 15N R 08W D-07
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

'98 OCT 19 A8:55

Signature of Register of Deeds

Register of Deeds Stamp & File Number

- 4 Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13

I, JAMES G. KNAPP, in a field survey on JUNE 11, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN DEC. 1838, CORNER POST PLACED 39.98 CHAINS (2638.68 FEET) FROM N.E. CORNER AND N.W. CORNER, SECTION 20, AND WITNESSED: PINE 18" S23°W 19 LINKS (12.54 FEET) BEECH 10" N11°E 28 LINKS (18.48 FEET)

IN 1896, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE MARTINY TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R8W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 290 AND 291. CORNER IS LISTED AS, "PINE STUMP 30" S25°E 31 OLD CORNER REWITNESSED".

CORNER RECORDED AS PER P. A. 74 OF 1970, BY DUANE F. WOOD, P.S. 24625, ON MAY 14, 1990, IN LIBER 2, PAGE 330, AND NOTED AS, "FOUND STEEL BAR IN ROAD INTERSECTION", AND WITNESSED: P. POLE AZ. 355° 42.15 16" PINE AZ 140° 55.95 8" PINE AZ. 215° 43.65

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 of 1990

Signature of James G. Knapp, Chairman, DATE Oct. 10, 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" RE-BAR, AT ROAD SURFACE, AND AT 8" DEEP FOUND 1/2" x 30" IRON ROD INSIDE A STACK OF (3), 3" X 12" CHARCOAL FILLED VITIFIED CLAY TILES, 3.3' SOUTH OF CENTERLINE OF 15 MILE ROAD (20' BITUMINOUS), AND IN LINE WITH 105TH. AVENUE (14' GRAVEL) - SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-07, 1/4 CORNER COMMON TO SECTIONS 17 AND 20, T15N-R08W. FOUND 5/8" RE-BAR, AND 1/2" x 30" IRON ROD INSIDE A STACK OF (3), 3" X 12" CHARCOAL FILLED VITIFIED CLAY TILES AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE 1/2" x 30" IRON ROD AND INSIDE OF THE VITIFIED CLAY TILES, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED: FOUND NAIL IN S.W. SIDE OF 14" JACK PINE AZ. 152°, 55.84 FEET SET 60d SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF 14" WHITE PINE AZ. 212°, 59.12 FEET SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF UTILITY POLE AZ. 240°, 62.14 FEET SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF UTILITY POLE AZ. 322°, 54.85 FEET

Signed by James G. Knapp Surveyor's Michigan License No. 25853

Date OCTOBER 12, 1997

