

**SURVEY & REMONUMENTATION**

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

APR 26 1996  
COMMISSION

CORNER APPROVED BY PEER GROUP ON NOVEMBER 2, 1996

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

'96 APR 17 AIO:53

For corners in MECOSTA (County) Located In: Corner Code #

1. Public Land Survey T 15N R 08W E-3  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4 Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Joann Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, JAMES G. KNAPP, in a field survey on OCTOBER 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Only one corner may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**


DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN DEC. 1838. CORNER POST PLACED 40.00 CHAINS (2640 FEET) FROM 1/4 CORNER, SECTION 8, and 9 AND WITNESSED:  
 ELM 10" N43°E 19 LINKS (12.54 FEET)  
 BEECH 8" S23°W 23 LINKS (15.18 FEET)

IN 1896, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE MARTINY TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R8W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 290 AND 291. NOTES SHOW "AT CENTER OF ROADS = PLACE OF OLD CORNER".

ROAD SURVEY NOTES AT THE MECOSTA COUNTY ROAD COMMISSION, DATED JULY 1919, CALL FOR "TILE FOR SECTION CORNER", AND BEING AT STATION 0+00 WITH A (MAG. BEARING) OF S89°-30'E AND WITNESSED: 10" POPLAR S49°E 36'4"  
 14" POPLAR S46°W 34'6"

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1/2" IRON ROD, BURIED 1" DEEP, 1.4' SOUTH OF CENTERLINE OF 17 MILE (22' BITUMINOUS) AND IN LINE WITH 100th. AVE. (NORTH).



APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 of 1990  
*James G. Knapp*  
 CHAIRMAN  
 DATE Nov. 2, 1996

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3 - SECTION CORNER COMMON TO SECTIONS 4, 5, 8, AND 9, T15N-R08W  
 FOUND 1/2" IRON ROD AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. REMOVED THE 1/2" IRON ROD AND SET IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AND A HIGHWAY MONUMENT BOX.  
 TELEPHONE PEDESTAL  
 SET 60p SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF UTILITY POLE AZ. 52° 48.8 FEET  
 SET 60p SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF 8" ASH AZ. 171°, 50.76 FEET  
 SET 60p SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF UTILITY POLE AZ. 202°, 70.38 FEET  
 SET 60p SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF UTILITY POLE AZ. 344°, 156.34 FEET

Signed by James G. Knapp Date APRIL 15, 1996  
 Surveyor's Michigan License No. 25853