

SURVEY &
REMONUMENTATION MECOSTA COUNTY REMONUMENTATION PROGRAM

MAY 05 1997 CORNER APPROVED BY PEER GROUP ON OCTOBER 24, 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MECOSTA Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 15N R 08W E-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED FOR RECORD

96 OCT 29 AM 1:12

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on SEPTEMBER 24, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST ON DEC. 19, 1838. AND WITNESSED:
 BEECH 10" N26°E 51 LINKS
 PINE 24" N23°W 13 LINKS

IN 1896, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE MARTINY TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R08W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 290 AND 291. CORNER IS NOTED AS, "PINE STUMP 24" N23°W 13 LINKS = O.B.T., OLD STAKE AND CROCKERY."

SURVEY NOTES FROM SECTION 29 SUBDIVISION SHOW CORNER AS BEING 2634 FEET FROM S SEC. CORNER & 2654 FEET FROM E SEC. CORNER AND WITNESSED:
 E. BEECH 3" OF CLUMP N30°W 43.8'
 ELM 5" N55°E 37.5'

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION DATED JUNE 1919, BY H.F.A. NOTES CORNER AS "TILE" AND BEING AT STATION 0+0 AND WITNESSED:
 ELM 6" N56.25°E 37.2'
 ELM 6" N65.5°W 98.1'

CORNER CALLED FOR AS PER P.A. 132 SURVEY AS RECORDED IN LIBER 10, PAGE 697, BY GERALD J. GRAY, P.S. 17741. CORNER NOTED AS "FOUND 1.5" PIPE" AND WITNESSED:
 P POLE #163 N45°W 60.80'
 ELM STUMP N45°E 37.60'
 RD. SIGN S45°W 49.00'

CORNER CALLED FOR AS PER P.A. 74 AS RECORDED IN LIBER 2, PAGE 136, ON SEPT. 25, 1985 BY PHINEAS J. WOOD, P.S. 24625, "FOUND 1.5" PIPE - ACCEPTED AS CORNER", AND WITNESSED:
 P. POLE #163 N45°W 60.80'
 ELM STUMP N45°E 37.60'
 RD. SIGN S45°W 49.00'

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990
James G. Knapp
 CHAIRMAN
 DATE OCT. 24, 1996

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 18" OF 1.5" WELL POINT, BURIED 10" BELOW ROAD SURFACE. REMOVED WELL POINT AND DUG TO 44", FOUND NOTHING ELSE. PLACED 1.5" WELL POINT INSIDE OF COUNTY MONUMENT AND SET MONUMENT IN SAME LOCATION. CORNER IS 1.5' N. OF CENTERLINE OF 13 MILE RD. (21' BITUMINOUS), AND IN LINE W/ 100TH AVE. (22' GRAVEL) SOUTH. FOUND REMAINS OF ELM STUMP @ AZ. 42° 32.6'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-11 SECTION CORNER COMMON TO SECTIONS 28, 29, 32 AND 33, T15N-R08W.
 FOUND 18" OF 1.5" WELL POINT, BURIED 10" BELOW ROAD SURFACE, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 SET COUNTY REMONUMENTATION MONUMENT (WITH 1.5" WELL POINT INSIDE) AND HIGHWAY MONUMENT BOX IN SAME LOCATION AND WITNESSED:
 FOUND SPIKE IN W. SIDE CORNER FENCE POST AZ. 10°, 28.70'
 SET 60d SPIKE W/ REMONUMENTATION TAG W. SIDE 8" BOX ELDER AZ. 169°, 83.39'
 SET 60d SPIKE W/ REMONUMENTATION TAG N. SIDE UTILITY POLE AZ. 260°, 136.26'
 FOUND SPIKE IN N.E. SIDE UTILITY POLE #DL163 AZ. 324°, 60.80'

Signed by James G. Knapp Date OCTOBER 11, 1996
 Surveyor's Michigan License No. 25853

