

SURVEY & REMONUMENTATION
MECOSTA COUNTY REMONUMENTATION PROGRAM

JUL 10 1997

COMMISSION

CORNER APPROVED BY PEER GROUP ON NOVEMBER 2, 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JUL -2 AM 1:35
 1997

Joanne Brown
 Register of Deeds
 Mecosta County

For corners in MECOSTA (County)	Located In:	Corner Code #
1. Public Land Survey	T 15N R 08W	F-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on OCTOBER 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN DEC. 1838, CORNER POST PLACED 39.93 CHAINS (2635.38 FEET) FROM SECTION CORNER, 4, 5, 8, and 9 AND WITNESSED:
 PINE 10" N11°W 19 LINKS (12.54 FEET)
 MAPLE 8" S39°E 27 LINKS (17.82 FEET)

IN 1896, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE MARTINY TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R8W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 290 AND 291. NOTES SHOW, "STAKE 37 L. SOUTH OF TILE - EQUAL MEASURE".

ROAD SURVEY NOTES AT THE MECOSTA COUNTY ROAD COMMISSION, DATED JULY 1919, CALL FOR 1/4 POST AND BEING AT STATION 25+65 AND WITNESSED: EAST ONE OF TWO SMALL POPPLES, S79°W 123'

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990
James G. Knapp
 CHAIRMAN
 DATE Nov. 2, 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 ON APRIL 28, 1997, DURING ROAD RECONSTRUCTION PROJECT, FOUND STACK OF (3) 3" X 12" VITIFIED CLAY TILES 30" BELOW EXISTING ROAD SURFACE, AND 2' EAST OF FENCE LINE - NORTH.
 AFTER BITUMINOUS PAVING ON JULY 1, 1997, CORNER IS 0.5' SOUTH OF CENTERLINE OF 17 MILE ROAD (22' BITUMINOUS).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 F-3 - 1/4 CORNER COMMON TO SECTIONS 4 AND 9, T15N-R08W
 SET A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AND A HIGHWAY MONUMENT BOX OVER THE VITIFIED CLAY TILES AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 S.W. CORNER OF HOUSE FOUNDATION (HOUSE No. 9464) AZ. 46°, 151.53 FEET
 SET 60d SPIKE W/REMONUMENTATION TAG IN SOUTH SIDE OF UTILITY POLE AZ. 79° 193.94 FEET
 SET 60p SPIKE W/REMONUMENTATION TAG IN N.W. SIDE OF UTILITY POLE AZ. 214°, 140.75 FEET
 CENTURY TELEPHONE PEDESTAL NO. L6300 AZ. 315°, 43.9 FEET
 SET 60p SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF CORNER FENCE POST AZ. 356°, 34.80 FEET

Signed by James G. Knapp Date JULY 1, 1997
 Surveyor's Michigan License No. 25853

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 28, 1971
 REVISED MAY 14, 1978
 REVISED JAN. 1988
 ADAPTED TO WORD PROCESSING MARCH 1995

