

SURVEY &
REMONUMENTATION

MECOSTA COUNTY REMONUMENTATION PROGRAM

JUL 1 0 1997

CORNER APPROVED BY PEER GROUP ON NOVEMBER 2, 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JUL -2 11:35

1997

COMMISSION

Joanne Brown
Register of Deeds
Mecosta County

For corners in <u>MECOSTA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 15N R 08W	G-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on OCTOBER 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN DEC. 1838. CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM 1/4 CORNER, SECTION 9 and 10 AND WITNESSED:
BEECH 10" S88°W 20 LINKS (13.24 FEET)
BEECH 15" S60°E 32 LINKS (21.12 FEET)

IN 1896, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE MARTINY TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R8W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 290 AND 291. CORNER NOTED AS, "IN CENTER OF ROADS AS FOUND BY JAUQUES".

ROAD SURVEY NOTES AT THE MECOSTA COUNTY ROAD COMMISSION, DATED JULY 1919, CALL FOR SECTION CORNER AND BEING AT STATION 51+37 AND WITNESSED: ANCHOR POST S40°-30'E 35'- 6"
PINE 12" S04°-40'E 191'

CORNER NOTED BY THE MECOSTA COUNTY ROAD COMMISSION ON MAY 2, 1968 AS, "1/2" IRON - FOUND", AND WITNESSED:
P. POLE AZ. 154°-46', 144.8'
30" MAPLE AZ. 279°-58', 256.9'

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
CHAIRMAN
DATE Nov. 2, 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" X 18" IRON ROD, BURIED 5" BELOW ROAD SURFACE, AND AT 20" DEEP FOUND PLOW POINT AND VITIFIED CLAY TILE, SURROUNDED BY ROCKS, IN CENTERLINE OF 17 MILE ROAD (22' BITUMINOUS - WEST AND 22' GRAVEL - EAST), AND 4' WEST OF CENTERLINE OF 90th. AVE. (22' BITUMINOUS).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-3 - SECTION CORNER COMMON TO SECTIONS 3, 4, 9, and 10, T15N-R08W
FOUND 1/2" X 18" IRON ROD, BURIED 5" BELOW ROAD SURFACE, AND AT 20" DEEP FOUND PLOW POINT AND VITIFIED CLAY TILE, SURROUNDED BY ROCKS, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. REMOVED THE 1/2" IRON ROD AND SET IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT AND A HIGHWAY MONUMENT BOX.
SET 60p SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF CORNER FENCE POST AZ. 42°, 63.72 FEET
SET 60p SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF UTILITY POLE AZ. 162°, 143.32 FEET
SET 60p SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF 3" MAPLE AZ. 194°, 181.44 FEET
SET 60p SPIKE W/REMONUMENTATION TAG IN S.W. SIDE OF UTILITY POLE AZ. 321°, 43.60 FEET

Signed by *James G. Knapp* Date JULY 1, 1997
Surveyor's Michigan License No. 25853

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 1984
REVISED JAN 1991
ADAPTED FOR REGISTERED LAND SURVEYORS

