

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

MAR 14 2000

CORNER APPROVED BY PEER GROUP ON DECEMBER 3, 1999 STATE OF MICHIGAN

**LAND CORNER RECORDATION CERTIFICATE**

COUNTY OF MECOSTA  
RECEIVED FOR RECORD

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

'99 DEC 10 P2:59

For corners in  
MECOSTA  
(County)

Located In: Corner Code #

1. Public Land Survey T 15N R 08W H-03  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

*Joann Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on DECEMBER 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN DEC. 1838. POST PLACED 39.99 CHAINS (2639.34 FEET) FROM SECTION CORNER 2,3,10, AND 11 AND WITNESSED: MAPLE 5" N03°E 8 LINKS (5.28 FEET)  
BIRCH 7" S45°W 13 LINKS (8.58 FEET)

IN 1896, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE MARTINY TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R8W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 290 AND 291. NOTES SHOW, " OLD STAKE - REWITNESSED". AND WITNESSED: PINE STUMP 30" N20°W 37 LINKS (24.42 FEET)  
MAPLE STUMP FOR B.T.

CORNER CALLED FOR IN DEPARTMENT OF NATURAL RESOURCES NOTES OF MARTINY LAKE WILDLIFE FLOODING PROJECT, DATED 1954 BY WILLIAM L. PADDISON, P.S. 7256, AND NOTED AS, "I.P. 3/25/52 OLD TILE C/L RD. WITH WIRE FENCE - NORTH", AND NOTES A DISTANCE OF 2666.6 TO CORNER 3, 4, 9 AND 10.

CORNER RECORDED AS PER P.A. 74 OF 1970 BY, GERALD J. GRAY, P.S. 17741, IN LIBER 1, PAGE 384 ON JAN. 25, 1978 AND NOTED AS "FOUND IRON", AND WITNESSED:  
4" POPLAR N70°W 62.92'  
10" TREE N45°E 33.81'  
4" POPLAR S50°W 25.96'

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990

*James G. Knapp*  
CHAIRMAN  
DATE DEC. 3, 1999


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1 1/2" PINCH PIPE, SURROUNDED BY STONES, WITH PIECES OF BROKEN GLASS, BURIED 6" BELOW ROAD SURFACE, AT 16" DEEP FOUND A STACK OF TWO VITRIFIED CLAY TILES, 3' FOOT NORTH OF CENTER OF 17 MILE ROAD (22' GRAVEL), AND 3' EAST OF FENCE LINE (NORTH AND SOUTH).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-03, 1/4 CORNER COMMON TO SECTIONS 3 AND 10, T15N-R08W  
FOUND 1 1/2" PINCH PIPE, SURROUNDED BY STONES, WITH PIECES OF BROKEN GLASS, BURIED 6" BELOW ROAD SURFACE, AT 16" DEEP FOUND A STACK OF TWO VITRIFIED CLAY TILES, 3' FOOT NORTH OF CENTER OF 17 MILE ROAD (22' GRAVEL), AND 3' EAST OF FENCE LINE (NORTH AND SOUTH), AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

FOUND SPIKE IN S.E. SIDE OF UTILITY POLE AZ. 52° 41.06 FEET  
4" WHITE OAK AZ. 258°, 96.90 FEET  
FOUND SPIKE W/TAG NO. 30104 IN WEST SIDE OF FENCE POST AZ. 356°, 24.57 FEET  
FOUND SPIKE W/TAG NO. 30104 IN S.W. SIDE OF 4" JUNE BERRY AZ. 304°, 54.53 FEET



Signed by James G. Knapp Date DECEMBER 3, 1999  
Surveyor's Michigan License No. 25853