

**SURVEY & REMONUMENTATION**

MAR 03 1999

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

CORNER APPROVED BY PEER GROUP ON AUGUST 14, 1998

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'98 DEC 28 A8:36

For corners in

MECOSTA  
(County)

Located In:

Corner Code #

- |                                    |   |     |   |     |      |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey              | T | 15N | R | 08W | I-11 |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
| 2. Property Controlling in Section | S |     | T |     |      |
|                                    | S |     | T |     |      |
| 3. Miscellaneous Property in Sec.  | S |     | T |     |      |
|                                    | S |     | T |     |      |

*Joanna Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4 Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5 Private Claims \_\_\_\_\_

I, JAMES G. KNAPP, in a field survey on APRIL 29, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Only one corner may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN FEB. 1838, CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM 1/4 CORNER COMMON TO SECTIONS 34 AND 35, AND WITNESSED:  
 MAPLE 10" N72°E 22 LINKS (14.52 FEET)  
 PINE 22" S09°E 21 LINKS (13.86 FEET)

IN 1896, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE MARTINY TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R9W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 290 AND 291. CORNER NOTED AS,  
 "PINE STUMP 20" N45°E 16 } OLD COR.  
 "PINE STUMP 26" S30°E 62 }

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, FOR RECONSTRUCTION OF COUNTY ROAD 566, BY W. H. WRIGHT, DATED SEPT. 1949, AND NOTES CORNER AS: SEC. COR. AND P.I. OF C. IRON BAR AND STONES, STA. 251+61.57, WITH A DEF. 88°-24' LT., AND SHOWS A DISTANCE OF 2637.37' TO 1/4 CORNER 26 AND 27, AND 2654.46' TO 1/4 CORNER 26 AND 35.

CORNER RECORDED AS PER P.A. 74 OF 1970, BY JAMES L. FLETCHER, P.S. 19830, IN LIBER 1, PAGE 52 ON MAY 8, 1973, AS, "FOUND IRON", AND WITNESSED:  
 IDENT. CAP E. SIDE P. POLE N45°W 81.40'  
 P.K. W. SIDE P. POLE N25°E 101.25'  
 P.K. N. SIDE P. POLE S45°E 53.37'

CERTIFICATE OF SURVEYS AS PER P. A. 132 OF 1970, BY WILLIAM G. TINGLEY, P.S. 30104, RECORDED ON JUNE 27, 1995, IN LIBER 11, PAGE 926, AND RECORDED ON AUG. 29, 1995, IN LIBER 11, PAGE 974, CORNER NOTED AS, "END. IRON", AND WITNESSED:  
 ID CAP E SIDE PP N45°W 81.40'  
 PK W SIDE PP N25°E 101.25'  
 PK W SIDE PP S45°E 53.37'

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990

*James G. Knapp*  
CHAIRMAN  
DATE AUG. 14, 1998

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND RAILROAD SPIKE IN SURFACE OF BITUMINOUS ROAD INTERSECTION, AT 6" FOUND 3" X 20" PLOW SHARE ALONG SIDE 10" CIRCULAR X 24" STONE STANDING ON END, IN CENTERLINE OF 80<sup>TH</sup>. AVENUE (20' BITUMINOUS), AND 3.0' NORTH OF CENTERLINE OF 13 MILE ROAD (20' BITUMINOUS).

AT 3.0' NORTH, FOUND 1" X 24" PIPE, AT 3' DEEP FOUND LARGE PIECES OF CROCKERY AS IF BURIED THERE, BUT NOT INTENDED TO REPRESENT CORNER LOCATION (REMOVED).

SET HIGHWAY MONUMENT BOX DURING BITUMINOUS PAVING ON MAY 14, 1998.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-11, CORNER COMMON TO SECTIONS 26, 27, 34 AND 34, T15N-R08W.  
 FOUND RAILROAD SPIKE IN SURFACE OF BITUMINOUS ROAD INTERSECTION, FOUND 3" X 20" PLOW SHARE ALONG SIDE 10" CIRCULAR X 24" STONE, STANDING ON END, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
 REMOVED THE RAILROAD SPIKE, 3" X 20" PLOW SHARE, AND 10" CIRCULAR X 24" STONE, STANDING ON END, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:  
 SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF 8" BLACK OAK AZ. 60°, 176.53 FEET  
 TELEPHONE PEDESTAL AZ. 148°, 55.52 FEET  
 SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF UTILITY POLE AZ. 168°, 162.28 FEET  
 FOUND SPIKE IN N.E. SIDE OF UTILITY POLE AZ. 322°, 81.40 FEET

Signed by *James G. Knapp* Date OCTOBER 26, 1998

Surveyor's Michigan License No. 25853

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1983  
REVISED MAY 1983  
REVISED 1983  
ADAPTED FOR WORD PROCESSING, 1993

