

**SURVEY &
REMONUMENTATION**

MECOSTA COUNTY REMONUMENTATION PROGRAM

OCT 29 1998

CORNER APPROVED BY PEER GROUP ON AUGUST 14, 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

For corners in

MECOSTA
(County)

Located in:

Corner Code #

'98 OCT 19 A8:55

- | | | | | | |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 15N | R | 08W | I-12 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

James G. Knapp
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4 Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JAMES G. KNAPP, in a field survey on APRIL 29, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN FEB. 1838, CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM CORNER COMMON TO SECTIONS 34 AND 35, AND WITNESSED:
PINE 24" N76°W 18 LINKS (11.88 FEET)
PINE 10" N30°E 24 LINKS (15.84 FEET)

IN 1896, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE MARTINY TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R8W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 290 AND 291. CORNER NOTED AS,
"PINE STUMP 24" N30°W 36 {OLD COR. OW
"PINE STUMP 24" S20°W 53 {O.B.T. STUMP

CORNER USED BY, JAMES G. KNAPP, P.S. 25853, IN JOB NO. 90-121, WITH CORNER NOTED AS: W. 1/4 COR. "FD. IRON", AND SHOWS A DISTANCE OF 2618.43' TO S.E. CORNER SECTION 34.

CORNER USED BY, WILLIAM G. TINGLEY, P.S. 30104, IN JOB NO. 95116, WITH CORNER NOTED AS: 1/2" BAR 12" DEEP, AND SHOWS A DISTANCE OF 2618.62' TO S.E. CORNER SECTION 34.

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
CHAIRMAN
DATE AUG. 14, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAILROAD SPIKE IN BITUMINOUS SURFACE, AT 14" FOUND 1/2" IRON ROD INSIDE OF A STACK OF THREE (3) VITRIFIED CLAY TILES.

CORNER IS IN CENTER OF 80TH. AVENUE (22' BITUMINOUS), AND IN LINE WITH GARFIELD ROAD (14' GRAVEL - EAST), AND IN LINE WITH FENCE - WEST.


SET MONUMENT AND HIGHWAY MONUMENT BOX DURING BITUMINOUS PAVING ON MAY 14, 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12, 1/4 CORNER COMMON TO SECTIONS 34 AND 35, T15N-R08W
FOUND RAILROAD SPIKE IN BITUMINOUS SURFACE, AT 14" DEEP FOUND A 1/2" IRON ROD INSIDE OF A STACK OF THREE (3) VITRIFIED CLAY TILES, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
REMOVED THE RAILROAD SPIKE, AND SET OVER THE 1/2" IRON ROD INSIDE OF THE VITRIFIED CLAY TILES A STANDARD MECOSTA REMONUMENTATION MONUMENT, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:
FOUND P.K. NAIL IN S.E. SIDE CORNER 10" POPLAR AZ. 46°, 40.92 FEET
TELEPHONE PEDESTAL AZ. 144°, 47.60 FEET
FOUND P.K. NAIL IN NORTH SIDE CORNER FENCE POST AZ. 272°, 35.12 FEET
SET 60d SPIKE W/REM. TAG IN N.E. SIDE UTILITY POLE AZ. 334°, 135.68 FEET

Signed by James G. Knapp
Surveyor's Michigan License No. 25853

Date OCTOBER 12, 1998



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993