

OCT 25 1999

MECOSTA COUNTY REMONUMENTATION PROGRAM

SECTION

CORNER APPROVED BY PEER GROUP ON NOVEMBER 13, 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

For corners in

MECOSTA (County)

Located In:

Corner Code #

'99 AUG 27 A9:25

- 1. Public Land Survey T 15N R 10W B-01
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Joann Brown REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4 Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13 containing numbers 1-36.

I, JAMES G. KNAPP, in a field survey on OCTOBER 19, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET BY DEPUTY SURVEYORS.

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY GERALD J. GRAY, P.S. 17741, RECORDED ON AUG. 10, 1977, IN LIBER 10, PAGES 417 - 419, AND NOTES CORNER AS, "NORTH 1/4 CORNER, SECTION 6 T15N R10W".

CORNER RECORDED AS PER P.A. 74 OF 1970, BY GERALD J. GRAY, P.S. 17741, IN LIBER 2, PAGE 237, ON NOV. 14 1988 AND NOTED AS, "SET 1/2" STEEL ROD AT PRORATED DISTANCE ON TOWNSHIP LINE 214.80 FEET WEST OF THE SOUTH 1/4 CORNER OF SECTION 31, T16N,R10W ON LINE WITH THE COMMON TOWNSHIP CORNER", AND WITNESSED:

- 10" ASH AZ. 196° 17.95
TWIN MAPLE AZ. 319° 22.63
MAPLE CLUSTER AZ. 18° 23.57

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY GERALD J. GRAY, P.S. 17741, RECORDED ON DEC. 13, 1985, IN LIBER 11, PAGE 180, AND NOTES CORNER AS, "NORTH 1/4 CORNER NOT SET PRORATED", AND SHOWS A DISTANCE OF 214.80', EAST TO THE SOUTH 1/4 CORNER, SECTION 31, T16N-R10W

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 346 OF 1990 James G. Knapp CHAIRMAN DATE Nov. 13, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-BAR, WITH CAP #17741 - 25625, IN CENTER OF 18 MILE ROAD (24' GRAVEL).

MEASURED DISTANCE TO B-13, T16N-R10W = 214.65', TO A-01 = 2200.26' AND TO C-01 = 2635.26'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-01, NORTH 1/4 CORNER SECTION 6, T15N-R10W.

FOUND 1/2" RE-BAR, WITH CAP #17741 - 25625, IN CENTER OF 18-MILE ROAD.

REMOVED THE 1/2" RE-BAR, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTMENT MONUMENT, AND WITNESSED:

- SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE 14" ELM AZ. 26°, 32.02 FEET
SOUTH 1/4 CORNER, SECTION 32, T16N-R10W (COUNTY REMONUMENTMENT MONUMENT) AZ. 90°, 214.65 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN S.W. SIDE 18" MAPLE AZ. 138°, 75.60 FEE
SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE TWIN 18" MAPLE AZ. 172°, 40.38 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE 14" MAPLE AZ. 308°, 64.38 FEE

Signed by James G. Knapp Surveyor's Michigan License No. 25853

Date JULY 21, 1999

