

1102
Field

A. Continued (C-13, T15N-R10W)

1976 +/- Ferris State College, Student Project

Found Sleigh Shoe

Poplar 8" N45°W 83.71 feet

Oak 18" N42°E 47.85 feet

Power Pole S37°E 81.10 feet

3/4" Iron Pipe West 13.80 feet Northeast Corner, Section 6, T14N-R10W

December 15, 1978, Thomas H. Sage, Field Notes

Found Railroad spike during Section breakdown of Section 5, T14N-R10W that was 13.80 feet East of the 3/4" Pipe, Northeast corner, Section 6, T14N-R10W

March 26, 1982, Pat Leemon, Surveyor, USFS Field Notes, Page 4A

Found Railroad Spike

Removed Railroad Spike and set 5" x 36" concrete Monument with Brass Cap.

10" Dock Spike in the Northwest side of White Oak 14" N50°E 47.41 feet

Power Pole S31°E 81.16 feet

10" Dock Spike in the Southeast side of White Oak 5" S41°W 83.92 feet

10" Dock Spike in the Southwest Side of White Pine 8" N33°W 87.58 feet

230th and 12 Mile Road Sign S57°W 52.76 feet

November 17, 1982, Robert A. Griffin, LS # 13584, LCRC Liber 2, Page 73

5" x 36" Concrete Monument with Brass Cap

White Oak 14" N50°E 47.41 feet

Power Pole S31°E 81.16 feet

White Oak 5" S41°W 83.92 feet

White Pine 8" N33°W 87.58 feet