

SURVEY & REMONUMENTATION COMMISSION
APR 10 1995

MECOSTA COUNTY REMONUMENTATION PROGRAM

Corner approved by Peer Group on May 12, 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED FOR RECORD

'94 AUG -3 P1:38

corners in

me cost a
 (County)

Located In:

Corner Code #

Public Land Survey Sec. T 15 N R 10 W D-13 Big Rapids
T R Township
T R
 Property Controlling S T R
 in Section S T R
 Miscellaneous S T R
 Property in Sec. S T R

Carl Waldron
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____ Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Thomas H. Sage a field survey on May 7, 1994,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 rent manual of survey instructions of the United States Department of the Interior, Bureau of Land
 nagement or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 ve were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 urt of Law, established, re-established, monumented, re-monumented, recovered, found as
 ressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

Description of original monument and accessories and/or subsequent restoration:
 ptember 26, 1937, John Hodgson, Deputy Surveyor, GLO Notes, Volume 2, Pages 222
 d 223.

- Set Quarter Section Post
- Beech 8" N65°E 21 links
- Beech 7" N71°W 21 links
- rch 26, 1982, Pat Leemon, Surveyor, USFS, Field Notes, Page 4A, 5 and 6
- ablished corner on Section Line by Single Proportionate Measurement
- ember 17, 1982, Robert A. Griffin, L.S. #13584, LCRC Liber 2, Page 73
- Set 5" x 36" Concrete Monument with Brass Cap
- Pine Post 4" North 32.73 feet
- B. Oak 8" N15°E 64.35 feet
- B. Oak 8" N38°W 68.66 feet

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 und Standard USFS Monument with Brass Cap 1" below surface and 4 feet +/- North of the Centerline of 12 Mile Road
 rom LCRC Liber 2 Page 73 (Griffin's) witnesses the monument should be approximately 0.2 +/- East of found location.
 We excavated around monument and discovered it to be leaning to the West. Monument apparently was pushed by
 a Road Commission truck while grading the roads. We recovered several pieces of broken concrete monument
 that had been placed around the monument as backfill. The recovered monument was 24" long which was the
 original length placed. I speculate that when the original monument was placed on March 26, 1982, the road base was
 still frozen. (The material is a silt/clay.) It appears that the monument was purposely shorter because of the frozen ground.

Set the monument per the witnesses of LCRC Liber 2 page 73.

x 24" concrete monument with brass cap, 4 feet North of Centerline of 12 Mile Road, 12" +/- below surface.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 andard USFS Monument with Brass Cap
 Pine Post 4" North 32.73 feet Spike
 Black Oak 8" N15°E 64.35 feet Spike
 Black Oak 8" N38°W 68.66 feet Spike
 Oak 5" S10°E 42.85 feet 60 d Nail with Remonumentation Tag East Side
 White Oak 30" S20°W 36.92 feet 60 d Nail with Remonumentation Tag East Side

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990
James S. Krayer
 CHAIRMAN
 DATE MAY 12, 1994

ument is accepted as a careful and faithful perpetuation of the position of the original corner.

ined by Thomas H. Sage Date June 10, 1994

urveyor's Michigan License No. 33139

