

MAR 03 1999

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

CORNER APPROVED BY PEER GROUP ON NOVEMBER 13, 1998

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'98 DEC 28 A8:31

For corners in

MECOSTA

(County)

Located In:

Corner Code #

1. Public Land Survey	T	15N	R	10W	E-01
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

*James Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, JAMES G. KNAPP, in a field survey on NOVEMBER 10, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, ABNER E. VANNESS, SET POST ON FEB. 16, 1838. POST PLACED 36.50 CHAINS (2409.00 FEET) FROM 1/4 CORNER, SECTIONS 4 AND 5, AND BEING 318 LINKS (209.88 FEET) WEST OF CORNER SECTIONS 32 AND 33, T16N-R10W, AND WITNESSED:  
SUGAR 8" S10°W 30 LINKS (19.80 FEET)  
SUGAR 10" S58°E 21 LINKS (13.86 FEET)

CORNER RECORDED AS PER P.A. 74 OF 1970, BY DOUGLAS W. HOOTH, P.S. 7966, IN LIBER 1, PAGE 268, ON JAN. 27, 1977 AND NOTED AS, "FOUND LARGE STONE ON LINE 1' X 1' X10", IN CTR. OF RD., & ON OLD FENCE LINE SOUTH. FITS OCCUPANCY. CHISELED "X" TOP STONE 226.18' WEST OF SEC. COR. COMM. TO 32 & 33 & ON LINE TO S 1/4 COR. OF SEC. 32. T16N, R10W 10-18-76, PLACED BROKEN PART OF PLOW SHARE ON EDGE WITH POINT TO SOUTH, ON EAST SIDE STONE", AND WITNESSED:

- S50°E 43.27' 5" W. CHERRY
- S30°E 29.46' 6" ASH
- N35°W 37.32' FENCE POST
- N80°E 101.36' 5" W. CHERRY

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990

*James G. Knapp*  
CHAIRMAN  
DATE NOV. 13, 1998

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1/2" X 7" RE-BAR OVER 16" SQUARE X 20" STONE WITH "X" CHISELED IN POINT WITH PLOW POINT ALONG EAST SIDE, 1.2' NORTH OF CENTERLINE OF 18 MILE ROAD (20' BITUMINOUS), AND IN LINE WITH FENCE ROW - SOUTH.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-01, CORNER COMMON TO SECTIONS 4 AND 5, T15N-R10W.  
FOUND 1/2" X 7" RE-BAR OVER 16" SQUARE X 20" STONE WITH "X" CHISELED IN POINT, WITH CAST IRON PLOW POINT ALONG EAST SIDE, IN SURFACE OF 18 MILE ROAD (20' BITUMINOUS), AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.  
REMOVED THE 1/2" RE-BAR, AND LEFT THE STONE IN PLACE, AND CUT A STANDARD MECOSTA COUNTY REMONUMENTMENT MONUMENT TO FIT OVER THE STONE, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:

- FOUND NAIL IN S.E. SIDE TWIN 10" ELM AZ. 56°, 30.00 FEET
- S.E. CORNER, SECTION 32, T16N, R10W(COUNTY REMONUMENTMENT MONUMENT) AZ. 92°, 226.05 FEET
- FOUND NAIL IN N.E. SIDE 12" ASH AZ. 148°, 29.41 FEET
- FOUND NAIL IN S.E. SIDE 10" ELM AZ. 248°, 55.57 FEET

Signed by James G. Knapp Date DECEMBER 21, 1998  
Surveyor's Michigan License No. 25853

