

SURVEY &  
REMONUMENTATION

MAR 03 1999

MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON NOVEMBER 13, 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

'98 DEC 28 A8:37

For corners in  
MECOSTA Located In: Corner Code #  
(County)

1. Public Land Survey T 15N R 10W F-01  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

*James Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on OCTOBER 19, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
CORNER NOT SET BY GOVERNMENT LAND OFFICE DEPUTY SURVEYORS.

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, DATED MAY 17, 1930, NOTE CORNER BEING AT STATION 0+00 WITH SOUTH 1/4 CORNER, SECTION 33, T16N-R10W, BEING AT STATION 1+94, AND WITNESSED:  
ELM 20" N2-1/2°W 33.9'  
ELM 24" S33°-15'E 37.9'

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 349 of 1990

*James G. Knapp*  
CHAIRMAN  
DATE Nov. 13, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" X 18" IRON ROD, BURIED 4" BELOW BITUMINOUS ROAD SURFACE, 1.3' SOUTH OF CENTERLINE OF 18 MILE ROAD (20' BITUMINOUS).

STATE PLANE COORDINATES ON NAD-83 MICH-SOUTH (LAMBERT) VALUES, AS DETERMINED BY GOURDIE/FRASER AND ASSOCIATES, AUGUST 1997, :  
NORTH = 814146.80'  
EAST = 12820001.33'  
WITH A DISTANCE OF 2661.79' TO G-01.

FOUND REMAINS OF ELM STUMP(1930 WITNESS TREE) AT AZ. 358°, 34.0 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-01, NORTH 1/4 CORNER SECTION 4, T15N-R10W.  
FOUND 3/4" X 18" IRON ROD, BURIED 4" BELOW BITUMINOUS ROAD SURFACE, 1.3' SOUTH OF CENTERLINE OF 18 MILE ROAD (20' BITUMINOUS).  
REMOVED THE 3/4" X 18" IRON ROD, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTMENT MONUMENT, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:  
FOUND SPIKE IN EAST SIDE 30" MAPLE AZ. 18°, 32.12 FEET  
SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE 26" MAPLE AZ. 62°, 61.14 FEET  
SOUTH 1/4 CORNER, SECTION 33, T16N-R10W (COUNTY REMONUMENTMENT MONUMENT) AZ. 92°, 193.65 FEET  
FOUND SPIKE IN S.E. SIDE 15" BOX ELDER AZ. 252°, 56.61 FEET  
FOUND SPIKE IN WEST SIDE 18" ELM AZ. 222°, 31.41 FEET

Signed by *James G. Knapp* Date OCTOBER 19, 1998  
Surveyor's Michigan License No. 25853

FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN 28, 1993  
REGISTERED PROFESSIONAL SURVEYOR  
ADAPTED FOR WORD PROCESSING, 1993

