

**SURVEY & REMONUMENTATION**  
**MECOSTA COUNTY REMONUMENTATION PROGRAM**

**OCT 29 1998** CORNER APPROVED BY PEER GROUP ON DECEMBER 12, 1997

**LAND CORNER RECORDATION CERTIFICATE**

STATE OF MICHIGAN  
 COUNTY OF MECOSTA  
 RECEIVED FOR RECORD

**SECTION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MECOSTA  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 15N R 10W G-06  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4 Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

'98 AUG 19 A9:53

*James Brown*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, JAMES G. KNAPP, in a field survey on JUNE 19, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Only one corner may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, ABNER E. VANNESS, SET POST ON FEB. 13, 1838. CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM CORNER COMMON TO SECTIONS 15, 16, 21, AND 22, AND WITNESSED: BEECH 6" S84°E 11 LINKS (7.26 FEET) BEECH 6" N84°E 5 LINKS (3.30 FEET)

\* CORNER RECORDED AS PER P.A. 74 OF 1970, BY JOHN D. HENRY, P.S. 14875, IN LIBER 1, PAGE 15, ON MAY 4, 1972, AS, "HAND-HOLE IN CENTER U.S. 131 AND CENTERLINE FULLER STREET EXTENDED", AND WITNESSED: HAND-HOLE MONUMENT BOX LISTED ABOVE

CORNER RECORDED AS PER P.A. 74 OF 1970, BY GERALD GRAY, P.S. 17741, IN LIBER 1, PAGE 164, ON MAR. 24, 1975, AS, "FOUND IRON", AND WITNESSED: 6' HIGH POST DUE N. 31.38' FENCE POST N40°E 44.08' FENCE POST DUE S. 6.62'

CORNER RECORDED AS PER P.A. 74 OF 1970, BY DUANE F. WOOD, P.S. 24625, IN LIBER 2, PAGE 175, ON APR. 7, 1987 AS, "FOUND 4" CONCRETE MONUMENT IN NORTH - SOUTH FENCE AND 33' SOUTH OF EAST FENCE", AND WITNESSED: 8" PINE N20°W 91.5 6" APPLE EAST 96.9 10" ELM N70°E 89.8

APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 OF 1990

*James G. Knapp*  
 CHAIRMAN  
 DATE DEC. 12, 1997

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 4" DIA. CONCRETE MONUMENT, FLUSH WITH GROUND, IN REMAINS OF NORTH AND SOUTH FENCE, AND 33.5' SOUTH OF FENCE CORNER WITH FENCE NORTH AND EAST, AND IS 5' +/- NORTH OF CENTERLINE OF FULLER AVENUE (EXTENDED 200' +/- FROM EAST).

STATE PLANE COORDINATES ON NAD-83 MICH-SOUTH (LAMBERT) VALUES, AS DETERMINED BY GOURDIE/FRASER AND ASSOCIATES, AUGUST, 1997 NORTH = 800662.62' EAST = 12822604.73'

WITH A DISTANCE TO G-05 OF 2691.42', TO H-06 OF 2644.54', AND TO G-07 OF 2636.22'

\* DOESN'T APPLY TO THIS CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-06, 1/4 CORNER COMMON TO SECTIONS 15 AND 16, T15N-R10W FOUND 4" DIA. CONCRETE MONUMENT, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

LEFT THE 4" DIA. CONCRETE MONUMENT AS FOUND, AND SET A CARSONITE WITNESS POST WEST 0.5', AND WITNESSED: FOUND P.K. NAIL W/WASHER IN EAST SIDE OF RAILROAD TIE FENCE POST AZ. 06°, 33.46 FEET FOUND SPIKE IN SOUTH SIDE OF UTILITY POLE AZ. 85°, 98.67 FEET SET 60d SPIKE W/REMONUMENTATION WITNESS TAG IN N.E. SIDE 6" WHITE BIRCH (TWIN) AZ. 156°, 153.64 FEET SET 60d SPIKE W/REMONUMENTATION WITNESS TAG IN N.E. SIDE 12" RED PINE AZ. 320°, 88.96 FEET

Signed by James G. Knapp Date APRIL 14, 1998  
 Surveyor's Michigan License No. 25853

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1974  
 REVISION MAY 14, 1988  
 REVISED LAW  
 ADAPTED FOR REGISTERED LAND SURVEYORS

